

ITEM DETAIL SUMMARY SHEET 3																							
LOCATION			GUARDRAIL						MISCELLANEOUS											REMARKS			
BEGIN MILE STA.	END MILE STA.	POS.	621.20	621.205	621.215	621.60	621.80	900.640	203.15	203.30	301.28	402.13	604.40	604.412	604.415	604.418	613.10	616.20	616.21				616.28
			S.B. G.R. GALV.	S.B. G.R. GALV. 8' POST	HD S.B. G.R. GALV. 8' POST	ANCHOR FOR S.B. RAIL	REMOVAL & DISPOSAL OF GUARDRAIL	ALUMINUM APPROACH RAILING	COMMON EXCAVATION	EARTH BORROW	SUBBASE OF CRUSHED GRAV. FINE GRADED	AGGREGATE SHOULDERS, RAP	CHAN ELEV OF DI, CB OR MH	REHAB DI, CB, OR MH, CLASS I	REHAB DI, CB, OR MH, CLASS II	REHAB DI, CB, OR MH, CLASS III	STONE FILL, TYPE I	GRANITE SLOPE EDGING	VERTICAL GRANITE CURB				C-I-P CONC. CURB, TYPE B
			LF	LF	LF	EACH	LF	LF	CY	CY	TON	TON	EACH	EACH	EACH	EACH	CY	LF	LF				LF
TOWN OF ST. JOHNSBURY U.S. ROUTE 2 (CONT.)																							
188+21		RT							2.8		2.6							12			CONSTRUCT SIDEWALK RAMP, TYPE 6		
201+96		RT							0.7		0.7								5.0		CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
202+76		RT							1.5		1.4										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
203+83		RT							2.2		2.1								14.5		CONSTRUCT SIDEWALK RAMP, TYPE 6		
204+67		RT							3.3		3.2								19.5		CONSTRUCT SIDEWALK RAMP, TYPE 6		
206+36		LT							0.6		0.5										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
206+36		RT							1.7		1.6								10.0		CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
206+72		LT							1.2		1.2										CONSTRUCT SIDEWALK RAMP, TYPE I		
209+36		RT							1.4		1.2										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
209+39		LT							1.0		0.9										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
215+31		RT							1.3		1.2										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
215+33		LT							0.8		0.7										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
216+13		RT							2.2		2.1								10.0		CONSTRUCT SIDEWALK RAMP, TYPE I		
216+42		RT							1.5		1.4								10.0		CONSTRUCT SIDEWALK RAMP, TYPE I		
218+67		RT							1.2		1.2										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
218+67		LT							0.8		0.9										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
220+14		LT							1.3		1.2										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
220+80		LT							1.0		0.9										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
221+00		LT							0.8		0.9										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
221+77		LT							1.5		1.4										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
221+77		RT							4.2		4.0								9.5		CONSTRUCT SIDEWALK RAMP, TYPE 6		
222+56		RT							4.9		4.7								21.0		CONSTRUCT SIDEWALK RAMP, TYPE 6		
226+38		LT							0.8		0.9										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
230+00		LT							1.5		1.4								10.0		CONSTRUCT SIDEWALK RAMP, TYPE I		
231+60		RT							3.9		4.9								20.0		CONSTRUCT NEW CURB AND SIDEWALK WITH A TYPE I RAMP SEE SHEET 57		
237+32.5	237+70.0	RT	14.5			1	13	25		25											INSTALL ANCHOR @ STA. 237+32.5; CONNECT TO NEW ALUMINUM APPROACH RAILING @ STA. 237+45.0; CONNECT NEW ALUMINUM APPROACH RAILING TO EXISTING ALUMINUM BRIDGE RAIL @ STA. 237+70.0		
237+47.0	237+74.0	LT					27	25													CONNECT NEW ALUMINUM APPROACH RAILING TO EXISTING ALUMINUM BRIDGE RAIL @ STA. 237+74.0		
238+37.0	238+74.5	RT	14.5			1	25	25		25											CONNECT NEW ALUMINUM APPROACH RAILING TO EXISTING ALUMINUM BRIDGE RAIL @ STA. 238+37.0; CONNECT TO NEW ALUMINUM APPROACH RAILING @ STA. 238+62.0; INSTALL ANCHOR @ STA. 238+74.5		
238+40.0	238+65.0	LT					12.5	25													CONNECT NEW ALUMINUM APPROACH RAILING TO EXISTING ALUMINUM BRIDGE RAIL @ STA. 238+40.0		
239+17		LT							0.8		0.7										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
241+53		LT							1.4		1.4										CONSTRUCT SIDEWALK RAMP, TYPE I		
241+93		LT							0.6		0.5										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
SHEET SUBTOTALS:			29			2	77.5	100	46.9	50	45.8							12	129.5	ITEM DETAIL SUMMARY SHEET #3 PROJECT NAME: ST. JOHNSBURY - LYNDON PROJECT NUMBER: STP 2936(1) FILE NAME: plc308.dgn PROJECT LEADER: G. EDWARDS DESIGNED BY: D. DRAPER PLOT DATE: 5/5/2014 DRAWN BY: D. DRAPER CHECKED BY: J. LITTLE SHEET 14 OF 250			