

ITEM DETAIL SUMMARY SHEET 14

LOCATION			MISCELLANEOUS																REMARKS	
BEGIN MILE STA.	END MILE STA.	POS.	616.35 TREATED TIMBER CURB LF	616.40 REMOVING & RESETTING CURB LF	616.41 REMOVAL OF EXISTING CURB LF	616.47 BIT. CONC. GUTTERS & ISLANDS TON	618.10 PORTLAND CEMENT CONC. S.W., 5 INCH SY	618.11 PORTLAND CEMENT CONC. S.W., 8 INCH SY	618.30 DETECTABLE WARNING SURFACE SF	619.17 YIELDING MARKER POSTS EACH	649.31 GEOTEXTILE UNDER STONE FILL SY	653.20 TEMPORARY EROSION MATTING SY	676.10 DELINEATOR WITH STEEL POST EACH	900.620 S.P. (PARKING METER) EACH	900.620 S.P. (PARKING METER POST) EACH	900.620 S.P. (REMOVE & RESET PRK. MTR.) EACH	900.620 S.P. (REMOVE PRK. MTR.) EACH	900.620 S.P. (REMOVE PRK. MTR. POST) EACH		
TOWN OF LYNDON U.S. ROUTE 5 (CONT.)																				
190+57.0	191+07.0	LT										25	1						INSTALL ANCHOR @ STA. 190+57.0; CONNECT TO EXISTING BRIDGE RAIL @ STA. 191+07.0	
TOWN OF LYNDON ALT. VT I22																				
0+00	54+85.92	LT&RT								8									QUANTITIES FOR USE AS DIRECTED BY THE ENGINEER.	
2+37		RT				0.3													CONSTRUCT PERPENDICULAR BITUMINOUS GUTTER, SEE DETAIL ON SHEET 56	
4+90		RT						11		12									CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACES (2)	
5+02		LT						2		6									CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
5+42		RT						4		6									CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
7+50		RT						2		6									CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
8+10		RT						3		6									CONSTRUCT SIDEWALK RAMP, TYPE 1	
11+70		RT						3		6									CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
12+35		RT						8		8									CONSTRUCT SIDEWALK RAMP, TYPE 1	
32+84		RT								7	14								CONSTRUCT SIDEWALK RAMP, TYPE 6	
32+84		LT								3	8								CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
33+75	33+93	LT					0.4												CONSTRUCT BITUMINOUS GUTTER, SEE DETAIL ON SHEET 56	
35+60		LT					0.3												CONSTRUCT PERPENDICULAR BITUMINOUS GUTTER, SEE DETAIL ON SHEET 56	
36+42		RT						4		10									CONSTRUCT SIDEWALK RAMP, TYPE 6	
40+83		RT					0.2												CONSTRUCT PERPENDICULAR BITUMINOUS GUTTER, SEE DETAIL ON SHEET 56	
49+04.0	51+54.0	LT	90									25	1						INSTALL ANCHOR @ STA. 49+04.0; CONNECT TO EXISTING BRIDGE RAIL @ STA. 51+54.0. INSTALL TREATED TIMBER CURB STA. 49+90 TO 50+80.	