

CONCRETE NOTES:

CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURES.

1. APPROACH SLABS- 5000 PSI

2. WINGWALLS-5000 PSI

3. ALL CONCRETE ABOVE WILL BE SUPPLIED BY CARROLL CONCRETE INC.

4. ALL CONCRETE MIX DESIGNS HAVE BEEN SUBMITTED BY CARROLL CONCRETE INC, COPIES ARE INCLUDED ON SHEET 16

7. APPROACH SLABS SHALL HAVE A TEXTURED BROOM FINISH.

8. WINGWALLS AND ABUTMENT POUR TOP WILL HAVE ROUGH FINISH.

8. ABUTMENTS AND APPROACH SLABS FORMS CAN BE REMOVED WHEN THE SPECIFIED CONCRETE HAS REACHED 85% OF ITS DESIGN STRENGTH. CURE WILL CONTINUE BASED ON TABLE 501.17A "CURING CONCRETE COMPONENTS" 7 DAYS OF CURING. PER SECTION 501.17(5)

9. ALL EXPOSED CONCRETE EDGES SHALL BE CHAMFERED 3/4"

10. ALL LIFTING DEVICES ARE GALVANIZED

11. USING REDUCED CONCRETE STRENGTH FOR THE LIFTING DESIGN PRODUCES A MORE CONSERVATIVE DESIGN.

REVISION # 1 11-19-13  
REVISION # 2 12-6-13

COLD RIVER BRIDGES, LLC 10 LANBRO LANE TEL 603-756-9300 WALPOLE, NH FAX 603-756-9303	
CAVENDISH ER BRF 0146(13)	
GENERAL NOTES	SHEET NUMBER
DATE: 10-30-13	14
scale:	