LOCATION			DROP INLETS			CURB & SIDEWALK				GUARDRAIL														REMARKS
			604.412	604.415		616.305	616.41	618.10	618.30	621.20	621.205	621.206	621.217	621.60	621.76	621.77	621.80	676.10						REFERENCE COMP. BINDER FOR GUARDRAIL SUMMARY (SHEET II-I4)
STA	STA	POS	REHAB. DI, CB, OR MH, CLASS I	REHAB. DI, CB, OR MH, CLASS II		BIT. CONCRETE CURB, TYPE A	REMOVAL OF EXISTING CURB	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	DETECT. WARNING SURFACE (DWS)	STEEL BEAM GUARDRAIL GALV.	STEEL BEAM GUARDRAIL GALV. W/8' POSTS	STEEL BEAM GUARDRAIL GALV/ NESTED	HD STEEL BEAM GUARDRAIL, GALV/NESTED W/8' POSTS	ANCHOR FOR STEEL BEAM RAIL	REPLACE GUARDRAIL POST ASSEMBLY	REPLACE GUARDRAIL BEAM UNIT	REMOVAL & DISPOSAL OF GUARDRAIL	DELIN. W/STEEL POST						
			EACH	EACH		LF	LF	SY	SF	LF	LF	LF		EACH	EACH	EACH	LF	EACH						
	PUTNEY																							
42+85.0	295+36.0	LT/RT	2	1											125	65								ESTIMATED QUANTITY TO BE USED AS DIRECTED BY THE ENGINEER
51+39.0	54+98.0	RT															359.0							
51+35.5	54+98.0	RT								366.5				2				2						ANCHOR @51+35.5, ANCHOR @ 54+98, SEE STANDARD G-1d
51+56.0	55+37.0	LT															381.0							
51+56.0	55+43.5	LT								29.0	362.5			2				2						ANCHOR @51+56, ANCHOR @ 55+43.5, SEE STANDARD G-1d
62+10.0	62+72.5	RT								79.5				1			62.5	1						REMOVE MELT, ANCHOR @ 62+10, SEE STANDARD G-1d, SEE NON-YIELDING OBJECT DETAIL ON SHEET 7 FOR POST SPACING
62+72.5	67+43.5	RT																						RETAIN GUARDRAIL (HEIGHT = 28.5")
67+43.5	67+81.0	RT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ 67+81, SEE STANDARD G-1d
131+71.0	132+08.5	RT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ 131+71, SEE STANDARD G-1d
132+08.5	143+57.0	RT																						RETAIN GUARDRAIL (HEIGHT = 28")
143+57.0	143+94.5	RT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ 143+94.5, SEE STANDARD G-1d
166+40.0	169+26.0	LT															339.5							
166+40.0	169+26.0	LT								354.0				2				2						ANCHOR @166+40, ANCHOR @ 169+26, SEE STANDARD G-1d
166+40.0	169+40.0	RT								304.0				2			300.0	2						ANCHOR @166+40, ANCHOR @ 169+40, SEE STANDARD G-1d
187+20.0	190+20.0	RT								29.0	275.0			2			300.0	2						ANCHOR @187+20, ANCHOR @ 190+20, SEE STANDARD G-1d
191+54.0	198+36.0	RT															682.0							
191+54.0	198+41.5	RT								691.5				2				2						ANCHOR @191+54, ANCHOR @ 198+41.5, SEE STANDARD G-1d
228+09.0	229+46.0	RT															137.0							
226+96.0	229+46.0	RT								29.0	225.0			2				2						ANCHOR @ 226+96, ANCHOR @ 229+46, SEE STANDARD G-1d
228+68.0	229+46.0	LT															78.0							
228+68.0	230+30.5	LT								166.5				2				2						ANCHOR @ 228+68, ANCHOR @ 230+30.5, SEE STANDARD G-1d
241+47.0	247+86.0	RT																						RETAIN GUARDRAIL (HEIGHT = 27")
247+86.0	250+26.0	RT															240.0							
247+86.0	250+23.5	RT								239.5				1				1						ANCHOR @ 250+23.5, SEE STANDARD G-1d
241+47.0	248+84.0	LT																						RETAIN GUARDRAIL (HEIGHT = 27")
248+84.0	256+44.0	LT															760.0							
248+84.0	256+46.5	LT								764.5				1				1						ANCHOR @ 256+46.5, SEE STANDARD G-1d
250+37.0	256+04.0	RT															586.0							
250+42.0	252+78.0	RT								239.5				1				1						ANCHOR @ 250+42, SEE STANDARD G-1d
252+78.0	256+03.0	RT								14.5	312.5			1				1						ANCHOR @ 256+03, SEE STANDARD G-1d
261+04.0	267+40.0	LT															636.0							
261+04.0	267+41.5	LT								641.5				2				2						ANCHOR @ 261+04, ANCHOR @ 267+41.5, SEE STANDARD G-1d
272+98.0	273+35.5	RT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ 272+98, SEE STANDARD G-1d
273+35.5	278+55.5	RT																						RETAIN GUARDRAIL (HEIGHT = 29") AND BITUMINOUS CURB
278+55.5	278+93.0	RT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ 278+93, SEE STANDARD G-1d
276+97.0	277+34.5	LT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ 276+97, SEE STANDARD G-1d
277+34.5	279+76.5	LT																						RETAIN GUARDRAIL (HEIGHT = 28")
279+76.5	280+14.0	LT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ 280+14, SEE STANDARD G-1d
SUBTOTAL SHEET 11			2	1		0.0	0.0	0	0	4225.0	1175.0	0.0	0.0	30	125	65	5123.5	30						

PROJECT NAME: PUTNEY WESTMINSTER
PROJECT NUMBER: STP 2946(I)

FILE NAME: zIIc344frm.dgn
PROJECT LEADER: P. SHEDD
DESIGNED BY: N. LEMAY
ITEM DETAIL SUMMARY SHEET I

PLOT DATE: 12/10/2013
DRAWN BY: W. GORDON
CHECKED BY: P. SHEDD