LOCATION			DROP INLETS			CURB & SIDEWALK				GUARDRAIL														REMARKS
			604.412	604.415		616.305	616.41	618.10	618.30	621.20	621.205	621.206	621.217	621.60	621.76	621.77	621.80	676.10						
STA	STA	POS	REHAB. DI, CB, OR MH, CLASS I	REHAB. DI, CB, OR MH, CLASS II		BIT. CONCRETE CURB, TYPE A	REMOVAL OF EXISTING CURB	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	DETECT. WARNING SURFACE (DWS)	STEEL BEAM GUARDRAIL GALV.	STEEL BEAM GUARDRAIL GALV. W/8' POSTS	STEEL BEAM GUARDRAIL GALV/ NESTED	HD STEEL BEAM GUARDRAIL, GALV/NESTED W/8' POSTS	ANCHOR FOR STEEL BEAM RAIL	REPLACE GUARDRAIL POST ASSEMBLY	REPLACE GUARDRAIL BEAM UNIT	REMOVAL & DISPOSAL OF GUARDRAIL	DELIN. W/STEEL POST						
			EACH	EACH		LF	LF	SY	SF	LF	LF	LF		EACH	EACH	EACH	LF	EACH						
WESTMINSTER																								
W0+00.0	W434+35.0	LT/RT	4	1											105	55								ESTIMATED QUANTITY TO BE USED AS DIRECTED BY THE ENGINEER
W51+40.0	W59+38.0	RT															798.0							
W49+52.5	W59+40.0	RT								29.0	992.5			2				2						ANCHOR @ W49+52.5, ANCHOR @ W59+40, SEE STANDARD G-1d
																								SEE NON-YIELDING OBJECT DETAIL ON SHEET 7 FOR POST SPACING
W61+97.0	W68+47.0	RT															650.0							
W61+47.0	W68+47.0	RT								54.0	680.0			2				2						ANCHOR @ W61+47, ANCHOR @ W68+47, SEE STANDARD G-1d
																								SEE NON-YIELDING OBJECT DETAIL ON SHEET 7 FOR POST SPACING
W74+30.0	W77+05.0	RT															275.0							
W74+30.0	W77+05.0	RT								29.0	265.0			2				2						ANCHOR @ W74+30, ANCHOR @ W77+05, SEE STANDARD G-1d
																								SEE NON-YIELDING OBJECT DETAIL ON SHEET 7 FOR POST SPACING
W116+50.0	W119+25.0	RT															275.0							
W116+50.0	W119+25.0	RT								279.0				2				2						ANCHOR @ W116+50, ANCHOR @ W119+25 SEE STANDARD G-1d
W119+52.5	W120+40.0	LT															87.5							
W119+52.5	W120+40.0	LT								91.5				2				2						ANCHOR @ W119+52.5, ANCHOR @ W120+40, SEE STANDARD G-1d
W119+64.5	W120+48.5	RT															84.0							
W119+64.5	W120+77.0	RT								116.5				2				2						ANCHOR @ W119+64.5, ANCHOR @ W120+77, SEE STANDARD G-1d
W126+08.0	W143+62.0	RT															1754.0							
W125+63.0	W143+75.5	RT								29.0	1787.5			2				2						ANCHOR @ W125+63, ANCHOR @ W143+75.5, SEE STANDARD G-1d
	BRIDGE 27																							
W144+18.0	W144+55.5	RT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ W144+18, SEE STANDARD G-1d
W144+55.5	W145+55.5	RT																						RETAIN GUARDRAIL (HEIGHT = 30")
W145+55.5	W147+55.5	RT															200.0							
W145+55.5	W147+55.5	RT									200.0													
W147+55.5	W149+76.5	RT																						RETAIN GUARDRAIL (HEIGHT = 30")
W149+76.5	W150+14.0	RT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ W150+14, SEE STANDARD G-1d
	BRIDGE 27																							
W145+90.0	W146+27.5	LT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ W145+90, SEE STANDARD G-1d
W146+27.5	W150+62.5	LT																						RETAIN GUARDRAIL (HEIGHT = 28.5")
W150+62.5	W151+00.0	LT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ W151+00, SEE STANDARD G-1d
W159+55.0	W161+91.0	RT															236.0							
W159+40.0	W160+15.0	RT								77.0				1				1						ANCHOR @ W159+40, USE 11:1 TAPER
W160+15.0	W161+52.5	RT									137.5													
W161+52.5	W161+90.0	RT								39.5				1				1						ANCHOR @ W161+90, SEE STANDARD G-1d
W159+94.0	W162+77.0	LT															283.0							
W159+90.0	W160+40.0	LT								52.0				1				1						ANCHOR @ W159+90, USE 11:1 TAPER
W160+40.0	W162+40.0	LT									200.0													
W162+40.0	W162+90.0	LT								52.0				1				1						ANCHOR @ W162+90, SEE STANDARD G-1d
W208+84.0	W209+31.0	RT					47.0																	
W209+99.0	W210+24.0	RT					25.0																	
W209+31.0	W209+68.5	LT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ W209+31, SEE STANDARD G-1d
W209+68.5	W215+02.5	LT																						RETAIN GUARDRAIL (HEIGHT = 29.5")
W215+02.5	W215+40.0	LT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ W215+40, SEE STANDARD G-1d
W215+61.0	W215+98.5	LT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ W215+61, SEE STANDARD G-1d
W215+98.5	W217+80.5	LT																						RETAIN GUARDRAIL (HEIGHT = 29")
W217+80.5	W218+18.0	LT								39.5				1			37.5	1						REMOVE MELT, ANCHOR @ W218+18, SEE STANDARD G-1d
SUBTOTAL SHEET 12			4	1		0.0	72.0	0	0	1164.5	4262.5	0.0	0.0	26	105	55	4942.5	26						

PROJECT NAME: PUTNEY WESTMINSTER
PROJECT NUMBER: STP 2946(I)

FILE NAME: z11c344frm.dgn
PROJECT LEADER: P. SHEDD
DESIGNED BY: N. LEMAY
ITEM DETAIL SUMMARY SHEET 2

PLOT DATE: 12/10/2013
DRAWN BY: W. GORDON
CHECKED BY: P. SHEDD
SHEET 12 OF 138