LOCATION			DROP INLETS			CURB & SIDEWALK				GUARDRAIL													REMARKS
			604.412	604.415		616.305	616.41	618.10	618.30	621.20	621.205	621.206	621.217	621.60	621.76	621.77	621.80	676.10					
STA	STA	POS	REHAB. DI, CB, OR MH, CLASS I	REHAB. DI, CB, OR MH, CLASS II		BIT. CONCRETE CURB, TYPE A	REMOVAL OF EXISTING CURB	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	DETECT. WARNING SURFACE (DWS)	STEEL BEAM GUARDRAIL GALV.	STEEL BEAM GUARDRAIL GALV. W/8' POSTS	STEEL BEAM GUARDRAIL GALV/ NESTED	HD STEEL BEAM GUARDRAIL, GALV/NESTED W/8' POSTS	ANCHOR FOR STEEL BEAM RAIL	REPLACE GUARDRAIL POST ASSEMBLY	REPLACE GUARDRAIL BEAM UNIT	REMOVAL & DISPOSAL OF GUARDRAIL	DELIN. W/STEEL POST					
			EACH	EACH		LF	LF	SY	SF	LF	LF	LF		EACH	EACH	EACH	LF	EACH					
	VT 123																						
A0+00.0	A16+56.0	LT/RT	1												2								ESTIMATED QUANTITY TO BE USED AS DIRECTED BY THE ENGINEER
A14+10.0	A16+02.5	RT															192.5						
A14+15.0	A16+02.5	RT								189.5				1				1					ANCHOR @ A14+15, SEE STANDARD G-1d
A16+02.5	A16+53.0	RT																					RETAIN GUARDRAIL (HEIGHT = 28.5")
A14+78.5	A16+14.0	LT															135.5						
A14+76.5	A16+14.0	LT								139.5				1				1					ANCHOR @ A14+76.5, SEE STANDARD G-1d
A16+14.0	A16+53.0	LT																					RETAIN GUARDRAIL (HEIGHT = 28")
WESTMINSTER STATE																							
	HIGHWAY																						
C0+00.0	C40+65.0	LT/RT	3												53	25							ESTIMATED QUANTITY TO BE USED AS DIRECTED BY THE ENGINEER
C1+15.0	C3+91.0	RT															276.0						
C1+15.0	C3+90.0	RT								279.0				2				2					ANCHOR @ C1+15, ANCHOR @ C3+90, SEE STANDARD G-1d
C1+37.0	C4+64.0	LT															327.0						
C1+40.0	C4+65.0	LT								329.0				2				2					ANCHOR @ C1+40, ANCHOR @ C4+65, SEE STANDARD G-1d
NB RAMP	C11+07.0	RT																					RETAIN GUARDRAIL (HEIGHT = 28")
C11+07.0	C11+42.0	RT								62.5				1			60.0	1					ANCHOR @ C11+42, SEE STANDARD G-1d
C13+93.0	C14+30.5	RT								39.5				1			37.5	1					REMOVE MELT, ANCHOR @ C13+93, SEE STANDARD G-1d
C14+30.5	C18+79.5	RT																					RETAIN GUARDRAIL (HEIGHT = 30")
C18+79.5	C19+17.0	RT								39.5				1			37.5	1					REMOVE MELT, ANCHOR @ C19+17, SEE STANDARD G-1d
C21+20.5	C21+58.0	RT								39.5				1			37.5	1					REMOVE MELT, ANCHOR @ C21+20.5, SEE STANDARD G-1d
C21+58.0	C25+28.0	RT																					RETAIN GUARDRAIL (HEIGHT = 29")
C25+28.0	C25+65.5	RT								39.5				1			37.5	1					REMOVE MELT, ANCHOR @ C25+65.5, SEE STANDARD G-1d
C25+27.5	C25+65.0	LT								39.5				1			37.5	1					REMOVE MELT, ANCHOR @ C25+27.5, SEE STANDARD G-1d
C25+65.0	C35+70.5	LT																					RETAIN GUARDRAIL (HEIGHT = 29.5"")
C35+70.5	C36+08.0	LT								39.5				1			37.5	1					REMOVE MELT, ANCHOR @ C36+08, SEE STANDARD G-1d
C26+94.5	C27+32.0	RT								39.5				1			37.5	1					REMOVE MELT, ANCHOR @ C26+94.5, SEE STANDARD G-1d
C27+32.0	C35+77.0	RT																					RETAIN GUARDRAIL (HEIGHT = 29")
C35+77.0	C36+14.5	RT								39.5				1			37.5	1					REMOVE MELT, ANCHOR @ C36+14.5, SEE STANDARD G-1d
SUBTOTAL SHEET 11			2	1		0.0	0.0	0	0	4225.0	1175.0	0.0	0.0	30	125	65	5123.5	30					
SUBTOTAL SHEET 12			4	1		0.0	72.0	0.0	0.0	1164.5	4262.5	0.0	0.0	26	105	55	4942.5	26					
SUBTOTAL SHEET 13			0	0		216.0	0.0	1.8	8.0	2159.0	452.5	50.0	200.0	22	0	0	1356.0	22					
SUBTOTAL SHEET 14			4	0		0.0	0.0	0.0	0.0	1315.5	0.0	0.0	0.0	15	55	25	1291.0	15					
PROJECT SUBTOTAL			10	2		216.0	72.0	1.8	8.0	8864.0	5890.0	50.0	200.0	93	285	145	12713.0	93					
TOTAL ROUNDING			0	0		4.0	3.0	0.2	0.0	61.0	60.0	0.0	0.0	0	0	0	87.0	0					
PROJECT TOTAL			10	2		220.0	75.0	2.0	8.0	8925.0	5950.0	50.0	200.0	93	285	145	12800.0	93					

PROJECT NAME: PUTNEY WESTMINSTER
PROJECT NUMBER: STP 2946(I)

FILE NAME: z11c344frm.dgn
PROJECT LEADER: P. SHEDD
DESIGNED BY: N. LEMAY
ITEM DETAIL SUMMARY SHEET 4

PLOT DATE: 12/10/2013
DRAWN BY: W. GORDON
CHECKED BY: P. SHEDD
SHEET 14 OF 138