

QUANTITY SHEET 4

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	ROADWAY (NO FEDERAL/STATE)	TRAINING	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							2				2		EACH	REMOVAL OF EXISTING TRAFFIC CONTROL SIGNAL SYSTEM	678.45	-			SPECIAL PROVISION (COLD PLANING, BITUMINOUS PAVEMENT)
							5				5		EACH	REMOVE STREET LIGHT ASSEMBLY	679.24	-	40473.1	SY	MAINLINE
							1				1		EACH	STREET LIGHT ASSEMBLY	679.46	-	2805.7	SY	SIDE ROADS
							6				6		EACH	BRACKET ARM	679.47	-	421.2	SY	ROUNDING
							6				6		EACH	LUMINAIRE	679.50	-	43700	SY	TOTAL
							1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			SPECIAL PROVISION (9.5 MM SBS POLYMER-MODIFIED BITUMINOUS CONCRETE PAVEMENT)(PG 76-34)(SBS POLYMER)
							1	20			21		EACH	SPECIAL PROVISION (ADJUST ELEVATION OF VALVE BOX)	900.620	-	4355	TON	MAINLINE WEARING COURSE
							10				10		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620	-	507	TON	SIDE ROAD WEARING COURSE
							1				1		EACH	SPECIAL PROVISION (GNSS CONSTRUCTION INSPECTION EQUIPMENT)	900.620	-	38	TON	ROUNDING
							13				13		EACH	SPECIAL PROVISION (JUNCTION BOX, HEAVY DUTY)	900.620	-	4900	TON	TOTAL
							1				1		EACH	SPECIAL PROVISION (RELOCATE FLASHING BEACON, GROUND MOUNTED)	900.620	-			SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)
								4			4		EACH	SPECIAL PROVISION (REPLACEMENT OF VALVE BOX)	900.620	-	2452.8	TON	TRAFFIC MANAGEMENT
							1080				1080		LF	SPECIAL PROVISION (BARRIER FOR TEMPORARY TRAFFIC PROTECTION)	900.640	10.5	255.7	TON	MULTI USE PATH
							162				162		LF	SPECIAL PROVISION (BOX BEAM GUARDRAIL W/7 FEET POSTS)	900.640	1	41.5	TON	ROUNDING
							120				120		LF	SPECIAL PROVISION (ELECTRICAL CONDUIT SLEEVE FOR FUTURE DEVELOPMENT)	900.640	16	2750	TON	TOTAL
							305				305		LF	SPECIAL PROVISION (HORIZONTAL DIRECTIONAL DRILLING) (12" CASING PIPE)	900.640	-			SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)
							1				1		LS	SPECIAL PROVISION (BLUETOOTH OBSERVATION SYSTEM)	900.645	-	4355	TON	MAINLINE WEARING COURSE
							1				1		LS	SPECIAL PROVISION (GPS MACHINE CONTROL GRADING)	900.645	-	507	TON	SIDE ROAD WEARING COURSE
							1				1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650	-	179	TON	LEVELING COURSE
							43700				43700		SY	SPECIAL PROVISION (COLD PLANING, BITUMINOUS PAVEMENT)	900.675	421.2	13231	TON	INTERMEDIATE COURSES
							750				750		SY	SPECIAL PROVISION (GREEN PAVEMENT MARKINGS - BICYCLE LANE)	900.675	7	7181	TON	BASE COURSES
							2020				2020		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	23	247	TON	ROUNDING
							4900				4900		TON	SPECIAL PROVISION (9.5 MM SBS POLYMER-MODIFIED BITUMINOUS CONCRETE PAVEMENT)(PG 76-34)(SBS POLYMER)	900.680	38	25700	TON	TOTAL
							200				200		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST			
							2750				2750		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	41.5			
							25700				25700		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	247			

**SHEET HAS NOT BEEN UPDATED.
SEE SITEMANAGER / EBOOKS FOR
QUANTITIES UTILIZED ON THIS
PROJECT.**



PROJECT NAME:	SOUTH BURLINGTON-WILLISTON
PROJECT NUMBER:	NH 2944(I)
FILE NAME:	zld340frm.dgn
PROJECT LEADER:	G. EDWARDS
DESIGNED BY:	D. BARNES
QUANTITY SHEET 4	
PLOT DATE:	3/1/2017
DRAWN BY:	D. BARNES
CHECKED BY:	J. LITTLE
SHEET	44 OF 249