STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 15

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (In) FOUNDATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM * BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
WILLISTON U.S. ROUTE 2 (CONT.)																																				
82+98, RT		1	9	15	0.94 ✓																													RIO-3e	MOUNT NEW SIGN ON EXISTING PEDESTRIAN SIGNAL POLE USING NEW MOUNTING HARDWARE (INCIDENTAL TO SIGN)	X		
83+33, RT		1	9	15	0.94 ✓																													RIO-3e	MOUNT NEW SIGN ON EXISTING PEDESTRIAN SIGNAL POLE USING NEW MOUNTING HARDWARE (INCIDENTAL TO SIGN)	X		
	SHEET 93 SUBTOTALS SHEET 94 SUBTOTALS SHEET 95 SUBTOTALS														6.25 0.00 8.25	37.00 94.00 69.55	31.50 26.75 42.25																				
	SHEET 96 SUBTOTALS SHEET 97 SUBTOTALS SHEET 98 SUBTOTALS														8.25 7.75 0.00	115.50 82.09 77.58	0.00 27.75 0.00																				
	SHEET 99 SUBTOTALS SHEET 100 SUBTOTALS SHEET 101 SUBTOTALS														0.00 0.00 0.00	60.75 64.25 37.25	0.00 57.75 30.25																				
	SHEET 102 SUBTOTALS SHEET 103 SUBTOTALS SHEET 104 SUBTOTALS														0.00 18.50 0.00	51.40 42.00 120.75	0.00 16.00 13.00																				
	SHEET 105 SUBTOTALS SHEET 106 SUBTOTALS														0.00 0.00	98.66 139.98	0.00 0.00																				
	SHEET 93 SUBTOTALS SHEET 94 SUBTOTALS SHEET 95 SUBTOTALS SHEET 96 SUBTOTALS				6.42 48.59 62.76 52.79		8 2 1 1								~~10~~ ~~11~~ ~~10~~	~~38~~ ~~98~~ ~~76~~ ~~129~~	~~30~~ ~~27~~ ~~42~~																				
	SHEET 97 SUBTOTALS SHEET 98 SUBTOTALS SHEET 99 SUBTOTALS				47.76 46.82 38.28		1 1								~~10~~ 	~~85~~ ~~83~~ ~~66~~	~~31~~																				
	SHEET 100 SUBTOTALS SHEET 101 SUBTOTALS SHEET 102 SUBTOTALS SHEET 103 SUBTOTALS				54.51 47.36 30.24 61.96		1 1	4							 ~~20~~	~~98~~ ~~38~~ ~~57~~ ~~46~~	~~59~~ ~~30~~ ~~17~~								2	291										
	SHEET 104 SUBTOTALS SHEET 105 SUBTOTALS SHEET 106 SUBTOTALS SHEET 107 SUBTOTALS				67.67 71.01 77.52 1.88		1 1 1								 	~~120~~ ~~92~~ ~~144~~	~~14~~								2 2	277 235										
	PROJECT SUBTOTALS ROUNDING				715.57 0.43		19 -	4 -							49.00 ~~61~~ ~~1~~	1090.76 ~~1170~~ ~~5~~	245.25 ~~250~~ ~~3~~								6 -	803 7										
												FT	FT	FT	FT ~~62~~	FT ~~1175~~	FT ~~253~~		EA	LB	LB	LB		LB 810	LB	LB	LB								
												FT			FT ~~1490~~ 1385.01					LB			EA. 6	LB 810				EA.	EA.	LB					

* "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."

TOTALS	SF	SF	EA.	EA.
	716		19	4

PROJECT NAME: SOUTH BURLINGTON-WILLISTON
PROJECT NUMBER: NH 2944(I)

FILE NAME: z11d340frm.dgn
PROJECT LEADER: G. EDWARDS
DESIGNED BY: D. DRAPER
TRAFFIC SIGN SUMMARY SHEET 15

PLOT DATE: 2/15/2017
DRAWN BY: D. DRAPER
CHECKED BY: J. LITTLE
SHEET 107 OF 249