



KOR-N-SEAL® II FLEXIBLE CONNECTOR

Installation Chart



Connector P/N	Suggested Pipe O.D. Range Inches	Hole Size Range Inches		Connector Dimensions Inches			Pipe Clamp	
		A		B	C	D	Qty	P/N
S206-18L	15.000 — 15.625	17.98	18.13	15.875	16	10.50	2	I-282
S206-22	17.625 — 19.000	21.98	22.13	19.875	19	10.50	2	I-318
S206-22L	19.000 — 19.625			20	20		2	I-348
*S206-24A	18.000 — 19.500	23.98	24.13	21.875	18.75	12.00	4	I-180
S206-24	19.625 — 21.000			21	21		4	
S206-24L	21.000 — 21.625	23.98	24.13	21.875	22	10.50	4	I-180
S206-26	21.625 — 23.000			23	23		4	I-190
S206-26L	23.000 — 23.625	26.00	26.20	23.875	24	10.50	4	I-218
S206-28	23.625 — 25.000			25	25		4	
S206-28L	25.000 — 25.625	28.00	28.20	25.875	26	10.50	4	I-218
S206-30	25.625 — 27.000			27	27		4	I-218
S206-30L	27.000 — 27.625	30.00	30.20	27.875	28	10.50	4	I-242
S206-32	27.625 — 29.000			29	29		4	
S206-32L	29.000 — 29.625	32.00	32.20	29.875	30	10.50	4	I-242
S206-34	29.625 — 31.000			31	31		4	
S206-34L	31.000 — 31.625	34.00	34.20	31.875	32	10.50	4	I-258
S206-36	31.625 — 33.000			33	33		4	
S206-36L	33.000 — 33.625	36.00	36.20	33.875	34	10.50	4	I-282
S206-38	33.625 — 35.000			35	35		4	I-282
S206-38L	35.000 — 35.625	38.00	38.20	35.875	36	10.50	4	I-306
S206-40	35.625 — 37.000			37	37		4	
S206-40L	37.000 — 37.625	40.00	40.20	37.875	38	10.50	4	I-306
S206-42	37.625 — 39.000			39	39		4	I-318
S206-42L	39.000 — 39.625	42.00	42.20	39.875	40	10.50	4	I-348
S206-44	39.625 — 41.000			41	41		4	
S206-44L	41.000 — 41.625	44.00	44.20	41.875	42	10.50	4	I-348
S206-46	41.625 — 43.000			43	43		4	I-348
S206-46L	43.000 — 43.625	46.00	46.20	43.875	44	10.50	6	I-242
S206-48	43.625 — 45.000			45	45		6	I-242
S206-48L	45.000 — 45.625	48.00	48.20	45.875	46	10.50	6	I-258
S206-50	45.000 — 45.625			46	46		6	
S206-50L	45.625 — 47.000	50.00	50.25	47.250	47	10.50	6	I-258
S206-52	47.000 — 47.625			48	48		6	
S206-52L	47.625 — 49.000	52.00	52.25	49.250	59	10.50	6	I-282
S206-54	49.000 — 49.625			50	50		6	
S206-54L	49.625 — 51.000	54.00	54.25	51.250	51	10.50	6	I-282

* Molded

- Double Wedge is available for 22 to 48 inch sizes, but .500 inches must be subtracted from the "B" dimension thus limiting your pipe O.D. range by .500 inches. The Double Wedge is only available on the "L" connectors.
- Special sizes quoted upon request.
- 50 inch (or larger) Connectors have 2 Wedges or more.

Caution:

- All stubs awaiting pipe installation at a later date must be restrained.
- Assume that a proper backfill material is used in adverse conditions.
- Prior to any critical usage, contact NPC Customer Service 800-626-2180.



Manufactured under the following patents:
 U.S. 5,431,459 CAN. 2,004,749
 EU/GERMANY. EP0498118

www.npc.com

250 Elm Street • P.O. Box 301
 Milford, NH 03055, U.S.A.

Tel: 603-673-8680 • 800-626-2180 • Fax: 603-673-7271