




## 1-Way Assemblies


Designed to accommodate all traffic signals, with the exception of optically programmed. The Tallon Series Astro-Brac is designed to be tough and durable. It features all-axis adjustability and is designed to facilitate the mounting of any size signal to any size mast arm or pole.



### Astro-Brac Assy, Tallon Series, 1-Way Band Mount

AB-0618	Signal Section	Band Length	Coating
	1 = 1 Sec	29 = 29" Band	PNC = Process No Color
	2 = 2 Sec	36 = 36" Band	P__ = Paint
	3 = 3 Sec	42 = 42" Band	
	4 = 4 Sec	48 = 48" Band	
	5 = 5 Sec	56 = 56" Band	


Note:  
Stainless steel upgrade available: includes stainless clamp screw and slotted washer.  
Specify by including -SS in the part number, i.e., AB-0618-3-29-SS-PNC.



### Astro-Brac Assy, Tallon Series, 1-Way Cable Mount

AB-0617	Signal Section	Cable Length	Coating
	1 = 1 Sec	62 = 62" Cable	PNC = Process No Color
	2 = 2 Sec	84 = 84" Cable	P__ = Paint
	3 = 3 Sec	96 = 96" Cable	
	4 = 4 Sec		
	5 = 5 Sec		

Note:  
Stainless steel upgrade available: includes stainless cable and slotted washer.  
Specify by including -SS in the part number, i.e., AB-0617-3-62-SS-PNC.




### Astro-Brac Assy, Galaxy Series, 1-Way Cable Mount

AG-0125	Signal Section	Cable Length	Coating
	3 & 4	84	P-34 Black
	1 = 1 Sec	62 = 62" Cable	PNC = Process No Color
	2 = 2 Sec	84 = 84" Cable	P__ = Paint
	3 = 3 Sec	96 = 96" Cable	
	4 = 4 Sec		
	5 = 5 Sec		

Note:  
Stainless steel upgrade available: includes stainless cable and slotted washer.  
Specify by including -SS in the part number, i.e., AG-0125-3-62-SS-PNC.

Note: 1. All assemblies are supplied standard with stainless steel fasteners.  
2. See Reference Section for clamp kit pole diameters.  
3. See Reference Section for available paint colors.



Astro-Brac

