



Cluster Assemblies

The Atlas Large Capacity series of Astro-Brac can conceal one 3/4" diameter or two 5/8" diameter conduits. The cluster assemblies are designed to mount five-section heads to any size or shape of mast arm or pole.




Astro-Brac
 PELCO PRODUCTS, INC.




Astro-Brac Assy, Atlas Series, 5-Sec Cluster, Articulated Serrated Cable Mount

AS-0162 - -
 Cable Length Coating
 See Note PNC=Process No Color
 P__=Paint




Note:
 Cable Length: 62", 84", 96", 110", 120", 132", 144", 220", or 280".
 Stainless steel upgrade available: includes stainless cable and slotted washer.
 Specify by including -SS in the part number, i.e., AS-0162-62-SS-PNC.




Astro-Brac Assy, Atlas Series, 5-Sec Cluster, Articulated Serrated Tenon Mount

AS-0187 - -
 Cable Length Coating
 62=62" Cable PNC=Process No Color
 84=84" Cable P__=Paint
 96=96" Cable




Note:
 Stainless steel upgrade available: includes stainless cable and slotted washer.
 Specify by including -SS in the part number, i.e., AS-0187-62-SS-PNC.



Astro-Brac Assy, Galaxy Series, 5-Sec Cluster, Cable Mount

AG-0138 - - Black
 Cable Length Coating
 See Note PNC=Process No Color
 P__=Paint



Note:
 Cable Length: 62", 84", 96", 110", 120", 132", 144", 220", or 280".
 Stainless steel upgrade available: includes stainless cable and slotted washer.
 Specify by including -SS in the part number, i.e., AG-0138-62-SS-PNC.

- Note: 1. All assemblies are supplied standard with stainless steel fasteners.
 2. See Reference Section for clamp kit pole diameters.
 3. See Reference Section for available paint colors.