



GTX™ City LED Arrow Signal Modules

- 12 inch module

Mechanical Outline

Dimensions in inches. (mm) indicates metric equivalent



Operating Specifications

Parameter	Rating
Operating Temperature Range*	-40 to +74°C (-40 to +165°F)
Operating Voltage Range	80 to 135 V (60Hz AC)
Power Factor (PF)	> 90 %
Total Harmonic Distortion (THD)	< 20 %
Voltage Turn-Off (VTO)	35 V
Turn-On / Turn-Off Time	< 75msec
Lens & Shell Material	UV Stabilized Polycarbonate
Wiring	40in, 20 AWG, Color Coded with Strain Relief

*Operating Temperature Range per ITE 2005 section 3.3.2

Design Compliance

Test type	Compliance
Luminous Intensity	ITE VTCSH-LED Vehicle Arrow Traffic Signal Supplement, July 2007
Chromaticity	ITE VTCSH-LED Vehicle Arrow Traffic Signal Supplement, July 2007
Moisture Resistance	NEMA STD 250 Type 4 - 1991 Blown Wind Rain MIL-STD-810F method 506.4
Mechanical Vibration	MIL-STD-883 Method 2007
Electronic Noise	FCC Title 47 Sub. B Sec.15 ¹
Transient Voltage Protection	Sec. 2.1.6 NEMA TS2-2003, 300V, 2500W Sec. 2.1.6 NEMA TS2-2003, 600V, 10µF Sec. 2.1.8 NEMA TS2-2003
Controller Compatibility	ITE VTCSH-LED Vehicle Arrow Traffic Signal Supplement, July 2007
Wiring	NFPA 70, National Electric Code
Transient Suppression	Sec. 8.2 IEC 1000-4-5 & Sec. 6.1.2 ANSI/IEEE C62.41.2 - 2002, 3KV, 2Ω Sec. 8.0 IEC 1000-4-12 & Sec. 6.1.1 ANSI/IEEE C62.41.2 - 2002, 6KV, 30Ω

Product Information



Model Number	Size (in)	AC Voltage Nominal	Power* (W) Nominal	Wavelength* (nm) Dominant	Maintained Intensity (Cd) Minimum
DR6-RTAAN-VLA	12	120V - 60Hz	5	626	58
DR6-RCAAN-VLA	12	120V - 60Hz	5	626	58
DR6-YTAAAN-VLA	12	120V - 60Hz	9	589	146
DR6-YCAAN-VLA	12	120V - 60Hz	9	589	146
DR6-GTAAAN-VLA	12	120V - 60Hz	5	500	76
DR6-GCAAN-VLA	12	120V - 60Hz	5	500	76

All lamps available in tinted or clear lens.

¹ Class A

*Data shown is target specification undergoing validation testing

Distributed by:



GE Lighting • 1-888-MY-GE-LED • www.gelighting.com

1 - 8 8 8 - 6 9 - 4 3 - 5 3 3 for North America • or • + 1 . 2 1 6 . 2 6 6 . 2 4 1 9

Information provided is subject to change without notice. All values are design or typical values when measured under laboratory conditions. The GE brand and logo are trademarks of the General Electric Company. © 2015 GE.