STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL S.H.S.M.*	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
OPTION ITEMS																																				
BRADFORD US ROUTE 5																																				
STATION 1+45.0 RT U.S. ROUTE 5	R7-1L, NO PARKING	1	12	18	1.50						1					X		1															INSTALL NEW SIGN ON NEW POST	X		
STATION 1+59.6 RT U.S. ROUTE 5	W11-2, PEDESTRIAN SYMBOL	1					1				1					X		1															RELOCATE EXISTING SIGN ON NEW POST			
	W16-7P, ARROW, PLAQUE	1					1																										RELOCATE EXISTING SIGN ON NEW POST (SUB-MOUNT)			
STATION 2+07.0 RT U.S. ROUTE 5	R7-1R, NO PARKING	1	12	18	1.50						1					X		1															INSTALL NEW SIGN ON NEW POST	X		
BRISTOL VERMONT ROUTE 17																																				
SITE 1 VT ROUTE 17	W11-2, PEDESTRIAN SYMBOL (SEE PLAN FOR LOCATION)	2	30	30	12.50						2					X		1															INSTALL NEW SIGN ON NEW POST	X		
	W16-7P, ARROW, PLAQUE	2	24	12	4.00																												INSTALL NEW SIGN ON NEW POST (SUB-MOUNT)	X		
SITE 2 VT ROUTE 17	W11-2, PEDESTRIAN SYMBOL (SEE PLAN FOR LOCATION)	2	30	30	12.50						2					X		1															INSTALL NEW SIGN ON NEW POST	X		
	W16-7P, ARROW, PLAQUE	2	24	12	4.00																												INSTALL NEW SIGN ON NEW POST (SUB-MOUNT)	X		
SITE 2 VT ROUTE 17	W7-8, RESERVED PARKING	1	12	18	1.50						1					X		1															INSTALL NEW SIGN ON NEW POST	X		
BURLINGTON																																				
SITE 1 COLLEGE STREET	R7-8, RESERVED PARKING	1					1				1		X					1															RELOCATE EXISTING SIGN ON NEW POST			
	R7-201P, TOW-AWAY ZONE (PLAQUE)	1					1																										RELOCATE EXISTING SIGN ON NEW POST (SUB-MOUNT WITH THE PREVIOUS SIGN)			
SITE 7 PEARL STREET	W11-2, PEDESTRIAN SYMBOL	1	30	30	6.25						1		X					1															INSTALL NEW SIGN ON NEW POST	X		
	W16-7P, ARROW, PLAQUE	1	24	12	2.00																												INSTALL NEW SIGN ON NEW POST (SUB-MOUNT)	X		
												FT	FT 22.50	FT	FT	FT 101.50	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 45.75	SF	EA. 4	SF				FT 22.50			FT 101.50					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND THE "SIGN POST DESIGN GUIDELINE".

*STANDARD HIGHWAY SIGNS AND MARKINGS BOOK

PROJECT NAME: STATEWIDE
PROJECT NUMBER: STP SDWK(11)

FILE NAME: z11f116tss.dgn
PROJECT LEADER: E. ATKINS
DESIGNED BY: T. BIGELOW
TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 10/9/2013
DRAWN BY: A. SWEETMAN
CHECKED BY: E. ATKINS
SHEET 44 OF 53