

COMPOSITE QUANTITY SHEET 1

**STATE OF VERMONT
AGENCY OF TRANSPORTATION**

SUMMARY OF ESTIMATED QUANTITIES

ALBURGH NH SURF(35)					ALBURGH-COLCHESTER NH SURF(36)						QUANTITIES GRAND TOTAL		ITEMS	ITEM NO.	ROUNDING
ROADWAY	NON-GOV'T PARTICIPATION	FULL C.E.	ALTERNATE A	ALTERNATE B	ROADWAY	NON-GOV'T PARTICIPATION	BRIDGE	FULL C.E.	ALTERNATE A	ALTERNATE B	UNIT				
5550					45000						50550	LF	SHOULDER BERM REMOVAL	203.40	EST.
1					1						2	CY	TRENCH EXCAVATION OF EARTH, EXPLORATION (N.A.B.I.)	204.22	EST.
21000					7400						28400	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	525
33500					120000						153500	LF	MILLED RUMBLE STRIPS 	213.10	3670
2500					12500						15000	TON	AGGREGATE SHOULDERS	402.12	534
1					1						2	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
9000					55000						64000	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 234 (ASTM D 6690) TYPE II)	417.20	EST.
2750					12000						14750	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	406
1					1						2	LU	AIR VOIDS PAY ADJUSTMENT	490.31	-
							325				325	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	EST.
							100				100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.
5									4		9	EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-
					2						2	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
	9										9	EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-
25					100						125	HR	POWER GRADER RENTAL	608.15	EST.
150					700						850	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
100					200						300	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
100					200						300	HR	TRUCK RENTAL	608.37	EST.
	8				1						9	EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-
1900					3000						4900	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
2400					4000						6400	HR	FLAGGERS	630.15	EST.
		0.5						0.5			1	LS	FIELD OFFICE, ENGINEERS	631.10	-
		0.5						0.5			1	LS	TESTING EQUIPMENT, BITUMINOUS (N.A.B.I.)	631.17	-
		1500						1500			3000	DL	FIELD OFFICE, TELEPHONE (N.A.B.I.)	631.26	-
0.5					0.5						1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
1											1	LS	TRAFFIC CONTROL (NH SURF (35))	641.10	-
					1						1	LS	TRAFFIC CONTROL (STP SURF(36))	641.10	-
4					6						10	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
61000					358000						419000	LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	2111
61000					352000						413000	LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	2707
					1000						1000	LF	DURABLE 6 INCH WHITE LINE, POLYUREA	646.424	203
					300						300	LF	DURABLE 6 INCH YELLOW LINE, POLYUREA	646.434	143

REVISED 6/7/13

PROJECT NAME:	ALBURGH-COLCHESTER
PROJECT NUMBER:	NH SURF (35)/STP SURF(36)
FILE NAME: 12b320/12b322..dgn	PLOT DATE: 10-JUN-2013
PROJECT LEADER: FOWLER	DRAWN BY: PVT. MGT.
DESIGNED BY: PVT. MGT.	CHECKED BY: PAVT MGMT
IPARM FILE NAME: 12b322cpqs01.I	SHEET 4 OF 70