DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
BARTON US-5 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	W13-1	18	18		40 MPH						1																
NB	7.555	A	W1-2L	30	30			6.25								1		10'-9" X								INSTALL 300 FT NORTH OF EXISTING	X		
NB	7.574	A	W1-6	48	24		<=== LEFT LARGE ARROW						1	X															
NB	7.574	B	W1-6	48	24		RIGHT ===> LARGE ARROW			1				X															
NB	7.576	A	W1-6L	48	24			8.00										8'-4" X 9'-8"								INSTALL 10 FT SOUTH OF EXISTING	X		
NB	8.011	A/B	D3-1	34	12			2.83								1		7"-8" X								HEATH LN (TH-32); INSTALL BEHIND GUARDRAIL 6 FT OFF EDGE OF PAVEMENT		11	
NB	8.013	C	VR-017	24	30		LLL 16,000 LBS						1		X														
		C	VR-017	24	30			5.00								1		9"-6" X								HEATH LN (TH-32)		9	
NB	8.018	D	R1-1	30	30			6.25								1		9"-6" X								HEATH LN (TH-32); INSTALL AT END OF GUARDRAIL	X		
NB	8.019	A/B	D3-1	72	UNK.		HEATH LN						1		X														
		C/D	D3-1	72	UNK.		BARTON ORLEANS RD						1																
NB	8.570	A	W2-2ML	30	30		MODIFIED LEFT SIDE ROAD						1	X															
		A	W16-8A	30	18		LAKE REGION RD						1																
		A	W2-2L	30	30			6.25										12'-3" X									X		
		A	W16-8P	36	8			2.00																				6	
							SHEET TOTALS	36.58	0.00	1	0	0	7	0	0	4		60.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	294.6	0.0	55	4	3	70	0	0	50		750.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **BARTON-DERBY**
PROJECT NUMBER: **STPG SIGN(46)**

FILE NAME: **01 BARTON US 5 NB TSS.xls** PLOT DATE: **11/7/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
BARTON NB SHEET 7 SHEET **20** OF **100**