DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
BARTON US-5 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	M6-3	21	15		^UP ARROW US			1																		
		A	M3-4	24	12		WEST STATE			1																		
		A	M1-5	24	24		VERMONT 58 STATE			1																		
		A	M6-3	21	15		^UP ARROW STATE			1																		
		A	M3-3	24	12		SOUTH INTERSTATE			1																		
		A	M1-1	24	24		INTERSTATE 91 INTERSTATE			1																		
		A	M6-3	21	15		^UP ARROW INTERSTATE			1																		
		A	M1-1	24	24		INTERSTATE 91			1																		
		A	M3-1	24	12		NORTH INTERSTATE			1																		
		A	M6-1	21	15		RIGHT ---> INTERSTATE			1																		
NB	10.491	B	M3-1	24	12		NORTH INTERSTATE			1				X														
		B	M1-1	24	24		INTERSTATE 91 INTERSTATE			1																		
		B	M6-1	21	15		LEFT==> INTERSTATE			1																		
NB	10.520	J	R4-7	24	30		RIGHT BULLNOSE			1				X														
		K	OM1-1	18	18		YELLOW CLUSTER			1																		
							SHEET TOTALS	0.00	0.00	15	0	0	0	0	0	0		0.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	294.6	0.0	55	4	3	70	0	0	50		750.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **BARTON-DERBY**
PROJECT NUMBER: **STPG SIGN(46)**

FILE NAME: **01 BARTON US 5 NB TSS.xls** PLOT DATE: **11/7/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
BARTON NB SHEET 12 SHEET **25** OF **100**