DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
BARTON US-5 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	10.455	E	R1-1	30	30		STOP			1				X														
SB	10.441	F	M3-3	24	12		SOUTH US						1		X													
		F	M1-4	24	24		US 5						1															
		F	M3-3	24	12	BLK/ WHT	SOUTH	2.00								1		11′-6" X								X		
		F	M1-4	24	24	BLK/ WHT	5	4.00																		X		
SB	10.392	F	R2-1	24	30		SPEED LIMIT 50	5.00								1		10′-10" X							INSTALL 260 FT SOUTH OF ROUTE MARKER ASSEMBLY	X		
SB	10.277	F	W11-6H	30	30		HINGED SNOWMOBILE SYMBOL						1		X													
SB	10.028	F	VW-619	30	30		SHOULDER NARROWS						1		X													
		F	VW-619	30	30		SHOULDER NARROWS	6.25								1		11′-8" X									10	
SB	9.957	G	VR-017	24	30		LLL 24,000 LBS				1	1	1		X	1		10′-9" X							SALVAGE AND MOUNT ON NEW POSTS 10 FT BEYOND STREET NAME SIGN			
SB	9.956	E/F	D3-1	Varies	UNK.		INDUSTRIAL PK LN (TH-65)			1				X														
		G/H	D3-1	Varies	UNK.		BARTON-ORLEANS RD			1																		
SB	9.947	H	R1-1	30	30		STOP						1		X													
		H	R1-1	30	30		STOP	6.25								1		9′-10" X							INDUSTRIAL PARK LN (TH-65)	X		
SB	9.839	F	W10-3L	36	36		LEFT SIDE ROAD WITH TRACKS			1				X														
							SHEET TOTALS	23.50	0.00	4	1	1	6	0	0	5		75.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	282.6	0.0	47	4	3	63	0	0	38		570.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **BARTON-DERBY**
PROJECT NUMBER: **STPG SIGN (46)**

FILE NAME: **02 BARTON US 5 SB TSS.xls** PLOT DATE: **11/7/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
BARTON SB SHEET 3 SHEET **29** OF **100**