DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
IRASBURG US-5 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.293	A	VW-619	30	30		SHOULDER NARROWS						1		X													
		A	VW-619	30	30			6.25								1		10′-10" X									10	
NB	0.928	C	VR-017	24	30		LLL 24,000 LBS						1		X													
		C	VR-017	24	30			5.00								1		9′-3" X							STAGECOACH LN (TH-13)		9	
NB	0.933	D	R1-1	30	30		STOP						1		X													
		D	R1-1	30	30			6.25								1		10′-4" X							STAGECOACH LN (TH-13)	X		
NB	0.934	A/B	D3-1	UNK.	UNK.		STAGECOACH LN (TH-13)						1		X													
		A/B	D3-1	54	12			4.50								2		7′-9" X 8′-1"							STAGECOACH LN (TH-13)		11	
NB	1.815	N/A	N/A	N/A	N/A		EMPTY SIGN POST								X													
NB	2.161	C	VR-017	24	30		LLL 24,000 LBS						1		X													
		C	VR-017	24	30			5.00								1		11′-0" X							COOKS RD (TH-11)		9	
NB	2.161	A/B	D3-1	UNK.	UNK.		COOKS RD (TH-11)					1				1		8′-5" X							SALVAGE FROM EXISTING LOCATION; INSTALL 10 FT FROM EDGE OF PAVEMENT			
NB	2.169	A/B	D3-1	UNK.	UNK.		COOKS RD (TH-11)				1		1		X										SALVAGE AND INSTALL IN NEW LOCATION			
		D	R1-1	30	30		STOP						1															
		D	R1-1	30	30			6.25								1		10′-6" X							COOKS RD (TH-11)	X		
							SHEET TOTALS	33.25	0.00	0	1	1	7	0	0	8		120.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	133.1	0.0	19	1	1	32	0	0	26		390.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **BARTON-DERBY**
PROJECT NUMBER: **STPG SIGN (46)**

FILE NAME: **03 IRASBURG US 5 NB TSS.xls** PLOT DATE: **11/7/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
IRASBURG NB SHEET 4 SHEET **41** OF **100**