









DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS			EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION				
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN		REMOVE	1.75	2.00	2.50	FOUNDATION	3.00	3.50			4.00	5.00	SHSM	PROJECT SHEET #	STANDARD SHEET #
																	(LB / FT)				(LB / FT)								
IRASBURG US-5 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS							
NB	2.691 - 2.812	A/B	N/A	N/A	N/A		INSTALL (9) NEW DELINEATOR ASSEMBLIES															INSTALL 9 BACK TO BACK DELINEATOR ASSEMBLIES AT 100 FT SPACINGS. SEE SHEET 4. LAST DELINEATOR PLACED 58 FT SOUTH OF UTILITY POLE AT SE CORNER OF AIRPORT RD							
NB	2.737	A	W2-1	30	30			6.25							2	12'-3" X 13'-1"							INSTALL ADJACENT TO 2ND OF 3 UTILITY POLES WHICH ARE LOCATED DIRECTLY SOUTH OF AIRPORT RD INTERSECTION	X		6			
		A	W16-8P	48	15			5.00																	6				
NB	2.812	A/B	D3-1	38	12			3.17							1	7'-1" X							AIRPORT RD (TH-7); INSTALL 8 FT FROM EDGE OF PAVEMENT			12			
NB	2.815	C	VR-017	24	30		LLL 24,000 LBS				1																		
		C	VR-017	24	30			5.00							1	11'-2" X							AIRPORT RD (TH-7)			9			
NB	2.824	D	R1-1	30	30		STOP				1																		
		D	R1-1	30	30			6.25															AIRPORT RD (TH-7)	X					
NB	3.550	A	W11-4	36	36		CATTLE SYMBOL				1																		
NB	4.171		UNK.	UN.	UNK.		EMPTY SIGN POST															REMOVE EMPTY POST AT THIS LOCATION							
NB	4.285	A	W7-1	30	30	FY	STEEP GRADE				1																		
NB	4.329	A/B	D3-1	40	12			3.33							1	7'-0" X							CUTTING RD (TH-10); INSTALL 10 FT FROM EDGE OF PAVEMENT			12			
NB	4.336	C	VR-017	24	30			5.00							1	9'-7" X							CUTTING RD (TH-10); INSTALL 25 FT FROM EDGE OF PAVEMENT NOT NEW POST - 9'			9			
NB	4.342	A/B	D3-1	UNK.	UNK.		CUTTING RD (TH-10)				1																		
		D	R1-1	30	30			6.25							1	9'-6" X							CUTTING RD (TH-10)	X					
SIGN SUMMARY SHEET							SHEET TOTALS	40.25	0.00	0	0	0	5	0	0	7	105.0	0	0.0	0.0	0.0	0.0	PROJECT NAME: BARTON-DERBY PROJECT NUMBER: STPG SIGN (46)						
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	133.1	0.0	19	1	1	32	0	0	26	390.0	0		0.0			FILE NAME: 03 IRASBURG US 5 NB TSS.xl ; PLOT DATE: 11/7/2014 PROJECT MANAGER: D. BRYANT ; DRAWN BY: J. BLANCHARD DESIGNED BY: B. TOOTHAKER ; CHECKED: K. KERN IRASBURG NB SHEET 5; SHEET 42 OF 100						