DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
IRASBURG US-5 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	2.359	F	W1-2L	30	30		LEFT CURVE						1	X															
SB	2.340	F	W1-2L	30	30			6.25								1		13'-4" X								INSTALL 100 FT SOUTH OF EXISTING CURVE SIGN	X		
SB	2.164	G/H	D3-1	UNK.	UNK.		CAMPBELL RD (TH-20)						1		X														
		G	VR-017	24	30		LLL 24,000 LBS						1																
		H	R1-1	30	30		STOP						1																
		G	VR-017	24	30			5.00								1		9'-5" X								CAMPBELL RD (TH-20)		9	
SB	2.164	E/F	D3-1	42	12			3.50								1		6'-11" X								CAMPBELL RD (TH-20); INSTALL HALF WAY BETWEEN UTILITY POLE AND US-5		12	
SB	2.159	H	R1-1	30	30			6.25								1		9'-6" X								CAMPBELL RD (TH-20); INSTALL 30 FT OFF EDGE OF US 5 PAVEMENT	X		
SB	1.475	F	S3-1T	30	30		SCHOOL BUS STOP AHEAD						1		X														
		F	S3-1	36	36	FYG		9.00								2		11'-5" X 11'-8"									X		
SB	1.438	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X														
SB	1.341	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X														
SB	1.265	F	VW-133R	30	30			6.25								1		10'-5" X								INSTALL 400 FT SOUTH OF EXISTING HIDDEN DRIVE SIGN		10	
SB	0.357	F	R2-5A	24	18		REDUCED SPEED AHEAD						1		X														
		F	W3-5	36	36			9.00								2		10'-2" X 10'-8"									X		
SIGN SUMMARY SHEET							SHEET TOTALS	45.25	0.00	0	0	0	8	0	0	9		135.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	165.4	0.0	38	1	1	39	0	0	24		360.0		0	0.0								

PROJECT NAME: **BARTON-DERBY**
PROJECT NUMBER: **STPG SIGN (46)**

FILE NAME: **04 IRASBURG US 5 SB TSS.xls** PLOT DATE: **11/7/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
IRASBURG SB SHEET 2 SHEET **45** OF **100**