DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
DERBY US-5 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.853	J	R4-7	24	30		RIGHT BULLNOSE			1				X														
		J	OM1-1	18	18		YELLOW CLUSTER			1																		
		K	R3-4	36	36		NO U-TURN SYMBOL			1																		
NB	0.859	A	M3-1	24	12		NORTH US			1				X														
		A	M1-4	24	24		US 5			1																		
		A	M6-3	21	15		^UP US			1																		
		A	M3-2	24	12		EAST STATE			1																		
		A	M1-5A	30	24		VERMONT 105 STATE			1																		
		A	M6-3	21	15		^UP STATE			1																		
		A	M3-1	24	12		NORTH INTERSTATE			1																		
		A	M1-1	24	24		INTERSTATE 91 INTERSTATE			1																		
		A	M6-3	21	15		^UP INTERSTATE			1																		
		A	M3-3	24	12		SOUTH INTERSTATE			1																		
		A	M1-1	24	24		INTERSTATE 91 INTERSTATE			1																		
		A	M6-1	21	15		<--- LEFT INTERSTATE			1																		

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

SHEET TOTALS	0.00	0.00	15	0	0	0	0	0	0		0.0		0	0.0	0.0	0.0	0.0											
	SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB											
TOWN DIRECTIONAL TOTALS	184.3	0.0	104	3	1	53	0	0	30		450.0		0		0.0													

PROJECT NAME: **BARTON-DERBY**
PROJECT NUMBER: **STPG SIGN (46)**

FILE NAME: **07 DERBY US 5 NB TSS.xls** PLOT DATE: **11/7/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
DERBY NB SHEET 4 SHEET **74** OF **100**