DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
DERBY US-5 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.885	A	VR-921L	30	30		LEFT "ONLY"/THRU			1				X														
NB	0.901	A	VD1-1	72	12		^UP CANADA 5			1				X														
		A	VD1-1	72	12		<--- ST. JOHNSBURY 43			1																		
		A	M3-3	24	12		SOUTH INTERSTATE			1																		
		A	M1-1	24	24		INTERSTATE 91 INTERSTATE			1																		
		A	M6-1	21	15		<--- LEFT INTERSTATE			1																		
NB	0.903	C	M3-1	24	12		NORTH US			1				X														
		C	M1-4	24	24		US 5			1																		
		C	M6-1	21	15		<--- LEFT US			1																		
		C	M3-4	24	12		WEST STATE			1																		
		C	M1-5A	24	24		VERMONT 105 STATE			1																		
		C	M6-1	21	15		<--- LEFT STATE			1																		
		C	M3-3	24	12		SOUTH US			1																		
		C	M1-4	24	24		US 5			1																		
		C	M6-1	21	15		RIGHT ---> US			1																		
							SHEET TOTALS	0.00	0.00	15	0	0	0	0	0	0	0.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	184.3	0.0	104	3	1	53	0	0	30	450.0			0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **BARTON-DERBY**
PROJECT NUMBER: **STPG SIGN (46)**

FILE NAME: **07 DERBY US 5 NB TSS.xls**
PROJECT MANAGER: **D. BRYANT**
DESIGNED BY: **B. TOOTHAKER**
DERBY NB SHEET 5

PLOT DATE: **11/7/2014**
DRAWN BY: **J. BLANCHARD**
CHECKED **K. KERN**