| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS | | EXISTING SIGNS | | | | EXIST POST | | NUMBER OF NEW POSTS | SQUARE STEEL (IN) | | | TUBULAR STEEL Ø (IN) | | | | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | "A" | "B" | RETAIN | SALVAGE FROM | SALVAGE TO | REMOVE | RETAIN | REMOVE | | 1.75 (LB / FT) 1.88 | 2.00 (LB / FT) 2.42 | 2.50 (LB / FT) 3.35 | FOUNDATION | 3.00 (LB / FT) 7.60 | 3.50 (LB / FT) 9.00 | 4.00 (LB / FT) 10.80 | 5.00 (LB / FT) 14.60 | | | SHSM | PROJECT SHEET # | STANDARD SHEET # |
| **DERBY US-5 NB** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| | | C | M3-2 | 24 | 12 | | EAST STATE | | | 1 | | | | | | | | | | | | | | | | | | |
| | | C | M1-5A | 24 | 24 | | RIGHT ---> STATE | | | 1 | | | | | | | | | | | | | | | | | | |
| | | C | M6-1 | 21 | 15 | | VERMONT 105 STATE | | | 1 | | | | | | | | | | | | | | | | | | |
| NB | 0.911 | J | R4-7 | 24 | 30 | | RIGHT BULLNOSE | | | 1 | | | | X | | | | | | | | | | | | | | |
| | | J | OM1-1 | 18 | 18 | | YELLOW CLUSTER | | | 1 | | | | | | | | | | | | | | | | | | |
| | | K | R3-4 | 24 | 24 | | NO U-TURN SYMBOL | | | 1 | | | | | | | | | | | | | | | | | | |
| NB | 0.933 | A | VD1-1 | 72 | 12 | | ^UP DERBY CENTER 3 | | | 1 | | | | X | | | | | | | | | | | | | | |
| | | A | VD1-1 | 72 | 12 | | ^UP (45 DEG) CANADA 5 | | | 1 | | | | | | | | | | | | | | | | | | |
| NB | 1.010 | A | VR-921 | 30 | 30 | | LEFT ONLY/ THRU | | | 1 | | | | X | | | | | | | | | | | | | | |
| NB | 1.037 | A | VD1-1 | 72 | 12 | | ^UP DERBY CENTER 3 | | | 1 | | | | X | | | | | | | | | | | | | | |
| | | A | VD1-1 | 72 | 12 | | <-- LEFT CANADA 5 | | | 1 | | | | | | | | | | | | | | | | | | |
| | | A | M3-1 | 24 | 12 | | NORTH INTERSTATE | | | 1 | | | | | | | | | | | | | | | | | | |
| | | A | M1-1 | 24 | 24 | | INTERSTATE 91 INTERSTATE | | | 1 | | | | | | | | | | | | | | | | | | |
| | | A | M6-1 | 21 | 15 | | <-- LEFT INTERSTATE | | | 1 | | | | | | | | | | | | | | | | | | |
| NB | 1.060 | J | R4-7 | 24 | 30 | | RIGHT BULLNOSE | | | 1 | | | | X | | | | | | | | | | | | | | |
| | | | | | | | SHEET TOTALS | 0.00 | 0.00 | 15 | 0 | 0 | 0 | 0 | 0 | 0 | 0.0 | | | 0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | FT | | EA | LB | LB | LB | LB | | | | | |
| | | | | | | | TOWN DIRECTIONAL TOTALS | 184.3 | 0.0 | 104 | 3 | 1 | 53 | 0 | 0 | 30 | 450.0 | | | 0 | 0.0 | | | | | | | | |

## SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **BARTON-DERBY**
PROJECT NUMBER: **STPG SIGN (46)**

FILE NAME: **07 DERBY US 5 NB TSS.xls**
PROJECT MANAGER: **D. BRYANT**
DESIGNED BY: **B. TOOTHAKER**
DERBY NB SHEET 6

PLOT DATE: **11/7/2014**
DRAWN BY: **J. BLANCHARD**
CHECKED **K. KERN**
SHEET **76** OF **100**