DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
DERBY US-5 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	1.209	A	R2-1	24	30		SPEED LIMIT 35						1		X													
NB	1.248	A	VD-062AS	72	16		BUSINESS SIGN			1				X														
NB	1.279	A	R2-1	24	30			5.00								1		9'-9" X								INSTALL 164 FT NORTH OF BUSINESS SIGN, IN LINE WITH GIROUX AUTO SIGN	X		
NB	1.299	A/B	D3-1	Varies	12		JOSEPH ST (TH-57)						1		X													
		C	N/A	N/A	N/A		TH-57						1															
		A/B	D3-1	38	12			3.17								1		7'-1" X								JOSEPH ST (TH-57)		12	
NB	1.299	C	R2-1	24	30		SPEED LIMIT 25				1	1	1	X												SALVAGE AND REMOUNT BELOW LLL			
		C	VR-017	24	30		LLL 24,000 LBS						1															
		C	UNK.	UNK.	UNK.		SLOW CHILDREN AT PLAY				1		1													SALVAGE AND RETURN TO TOWN			
		C	VR-017	24	30			5.00																		JOSEPH ST (TH-57)		9	
NB	1.304	D	R1-1	30	30		STOP						1	X														
		D	R1-1	30	30			6.25																		JOSEPH ST (TH-57)	X		
NB	1.455	A	R2-1	24	30		SPEED LIMIT 35			1				X												REQUIRES VEGETATION CLEARING			
NB	1.741	A	R2-1	24	30		SPEED LIMIT 35			1				X														
NB	1.750	A/B	D3-1	Varies	12		BOUCHER CIRCLE (TH-19)						1		X													
							SHEET TOTALS	19.42	0.00	3	2	1	8	0	0	2		30.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	184.3	0.0	104	3	1	53	0	0	30		450.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **BARTON-DERBY**
PROJECT NUMBER: **STPG SIGN (46)**

FILE NAME: **07 DERBY US 5 NB TSS.xls**
PROJECT MANAGER: **D. BRYANT**
DESIGNED BY: **B. TOOTHAKER**
DERBY NB SHEET 8

PLOT DATE: **11/7/2014**
DRAWN BY: **J. BLANCHARD**
CHECKED **K. KERN**
SHEET **78** OF **100**