DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
DERBY US-5 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	M3-2	24	12		EAST STATE			1																		
		A	M1-5	30	24		VERMONT 105			1																		
		A	M6-1	21	15		RIGHT ---> STATE			1																		
		A	M4-5	24	12		TO STATE			1																		
		A	M1-5	30	24		VERMONT 111			1																		
		A	M6-1	21	15		RIGHT ---> STATE			1																		
NB	1.959	A	VR-925	36	30		LEFT "ONLY"/RIGHT "ONLY"			1				X														
NB	1.993	A	R1-1	30	30		STOP			1				X														
NB	2.009	C	W1-7	48	12		<====> DOUBLE ARROW			1				X														
NB	2.054	A	VD1-1	72	12		DERBY LINE 4			1				X														
		A	D2-1	72	12		CANADA 4			1																		
		A	M3-1	24	12		NORTH US			1																		
		A	M1-4	24	24		US5			1																		
		A	UNK.	UNK.	UNK.		NORTHEAST KINGDOM BYWAY			1																		
NB	2.097	A	R2-1	24	30		SPEED LIMIT 35			1				X														
							SHEET TOTALS	0.00	0.00	15	0	0	0	0	0	0	0.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	184.3	0.0	104	3	1	53	0	0	30	450.0			0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **BARTON-DERBY**
PROJECT NUMBER: **STPG SIGN (46)**

FILE NAME: **07 DERBY US 5 NB TSS.xls** PLOT DATE: **11/7/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
DERBY NB SHEET 10 SHEET **80** OF **100**