DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT)	2.00 (LB / FT)	2.50 (LB / FT)	FOUNDATION	3.00 (LB / FT)	3.50 (LB / FT)	4.00 (LB / FT)	5.00 (LB / FT)			SHSM	PROJECT SHEET #	STANDARD SHEET #
																	1.88	2.42	3.35		7.60	9.00	10.80	14.60					
DERBY US-5 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	VR-654	24	24		STRICTLY ENFORCED						1																
SB	3.839	F	R2-1	24	30		SPEED LIMIT 50						1		X														
SB	3.595	F	VW-054L	30	30		HIDDEN DRIVE LEFT						1		X														
		F	VW-081L	36	36		TRUCKS ENTERING LEFT						1																
SB	3.500	F	W11-10	30	30			6.25								1		10'-4" X								INSTALL 500 FT SOUTH OF EXISTING TRUCKS ENTERING SIGN	X		
SB	3.304	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X														
SB	3.236	F	W11-6H	30	30		HINGED SNOWMOBILE SYMBOL						1		X														
		F	W16-2	24	18		1000 FT						1																
SB	2.918	F	W3-5	36	36		SPEED REDUCTION SPEED LIMIT 35			1				X															
SB	2.809	F	R2-1	30	36		SPEED LIMIT 35			1				X															
SB	2.751	H	R2-1	30	30		SPEED LIMIT 50				1	1	1	X												BEEBE RD (TH-3); SALVAGE AND REMOUNT BELOW LEGAL LOAD SIGN			
		H	VR-079	24	24		LEGAL LOAD AS FOR STATE HIGHWAY						1																
		H	VR-079	24	30			5.00																	BEEBE RD (TH-3)		9	
SB	2.744	E/F	D3-1	34	12			2.83								1		7'-0" X								BEEBE RD (TH-3); INSTALL 8 FT FROM EDGE OF PAVEMENT, 37 FT SOUTH OF LLL		13	
SB	2.729	H	R1-1	30	30		STOP			1				X															
							SHEET TOTALS	14.08	0.00	3	1	1	9	0	0	2		30.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	261.5	0.0	99	6	5	69	0	0	38		570.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **BARTON-DERBY**
PROJECT NUMBER: **STPG SIGN(46)**
FILE NAME: **08 DERBY US 5 SB TSS.xls**
PROJECT MANAGER: **D. BRYANT**
DESIGNED BY: **B. TOOTHAKER**
DERBY SB SHEET 3
PLOT DATE: **11/7/2014**
DRAWN BY: **J. BLANCHARD**
CHECKED **K. KERN**
SHEET **86** OF **100**