DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
																	1.75	2.00	2.50		3.00	3.50	4.00	5.00				
																	(LB / FT)				(LB / FT)							
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.88	2.42	3.35	FOUNDATION	7.60	9.00	10.80	14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
DERBY US-5 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	M6-1	21	15		RIGHT ---> INTERSTATE			1																		
		F	M3-2	24	12		EAST STATE			1																		
		F	M1-5	30	24		VERMONT 105			1																		
		F	M6-3	21	15		^UP ARROW STATE			1																		
		F	M3-3	24	12		SOUTH US			1																		
		F	M1-4	24	24		US 5			1																		
		F	M6-1	21	15		RIGHT ---> US			1																		
		F	M4-5	24	12		TO STATE			1																		
		F	M1-5	30	24		VERMONT 111			1																		
		F	M6-3	21	15		^UP ARROW STATE			1																		
		F	M3-4	24	12		WEST STATE			1																		
		F	M1-5	30	24		VERMONT 105			1																		
		F	M6-1	21	15		RIGHT ---> STATE			1																		
SB	1.984	F	M3-3	24	12		SOUTH US			1				X														
		F	M1-4	24	24		US 5			1																		
							SHEET TOTALS	0.00	0.00	15	0	0	0	0	0	0		0.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	261.5	0.0	99	6	5	69	0	0	38		570.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: BARTON-DERBY
PROJECT NUMBER: STPG SIGN(46)

FILE NAME: 08 DERBY US 5 SB TSS.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
CHECKED BY: K. KERN
PLOT DATE: 11/7/2014
DRAWN BY: J. BLANCHARD