DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT)	2.00 (LB / FT)	2.50 (LB / FT)	FOUNDATION	3.00 (LB / FT)	3.50 (LB / FT)	4.00 (LB / FT)	5.00 (LB / FT)			SHSM	PROJECT SHEET #	STANDARD SHEET #
																	1.88	2.42	3.35		7.60	9.00	10.80	14.60					
DERBY US-5 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	M3-4	24	12		WEST STATE			1																		
		F	M1-5	30	24		VERMONT 105			1																		
		F	UNK	UNK	UNK		NEK BYWAY			1																		
SB	1.957	F	D2-1	72	12		NEWPORT 4			1				X														
SB	1.898	F	R2-1	24	30		SPEED LIMIT 35			1				X											REQUIRES VEGETATION CLEARING			
SB	1.753	E/F	D3-1	Varies	UNK.		KINGSBURY CR						1		X													
		H	R1-1	30	30		STOP				1	1	1			1		X										
SB	1.753	E/F	D3-1	64	12		Kingsbury Cir PVT	5.33								2		7'-1" X 7'-0"							KINGSBURY CIR (PVT); INSTALL 30 FT FROM END OF ROCKWALL, 8 FT FROM EDGE OF PAVEMENT		13	
SB	1.734	F	R2-1	24	30		SPEED LIMIT 35			1				X														
SB	1.588	E/F	D3-1	Varies	UNK.		ROY ST (TH-86)						1		X													
		E/F	D3-1	26	12		Roy St	2.17								1		7'-1" X							ROY ST (TH-86)		13	
SB	1.584	G	VR-017	24	30		LLL 24,000 LBS	5.00						X														
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		9'-6" X							ROY ST (TH-86)		9	
SB	1.582	H	R1-1	30	30		STOP						1	X														
		H	R1-1	30	30		STOP	6.25																	ROY ST (TH-86)	X		
SIGN SUMMARY SHEET							SHEET TOTALS	23.75	0.00	6	1	1	4	0	0	5		75.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	261.5	0.0	99	6	5	69	0	0	38		570.0		0	0.0							

PROJECT NAME: **BARTON-DERBY**
PROJECT NUMBER: **STPG SIGN(46)**

FILE NAME: **08 DERBY US 5 SB TSS.xls** PLOT DATE: **11/7/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
DERBY SB SHEET 7 SHEET **90** OF **100**