DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			SHSM	PROJECT SHEET #	STANDARD SHEET #
DERBY US-5 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	1.019	F	VR-921R	30	30		THRU/RIGHT "ONLY"			1				X														
SB	0.925	F	VD1-1	72	12		^UP NEWPORT 3			1				X														
		F	VD1-1	72	12		ST. JOHNSBURY 43 45 DEG==>			1																		
		F	M3-3	24	12		SOUTH INTERSTATE			1																		
		F	M1-1	18	18		INTERSTATE 91			1																		
		F	M6-1	21	15		RIGHT ---> (45 DEG) INTERSTATE			1																		
SB	0.908	E	M3-3	24	12		SOUTH INTERSTATE			1				X														
		E	M1-1	24	24		INTERSTATE 91			1																		
		E	M6-1	21	15		<--- LEFT INTERSTATE			1																		
SB	0.894	K	R4-7	24	30		RIGHT BULLNOSE			1				X														
		K	OM1-1	18	18		YELLOW CLUSTER			1																		
		J	R3-4	24	24		NO U-TURN SYMBOL			1																		
SB	0.868	F	M3-3	24	12		SOUTH US			1				X														
		F	M1-4	24	24		US 5			1																		
		F	M3-4	24	12		WEST			1																		
							SHEET TOTALS	0.00	0.00	15	0	0	0	0	0	0	0.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	261.5	0.0	99	6	5	69	0	0	38	570.0			0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **BARTON-DERBY**
PROJECT NUMBER: **STPG SIGN(46)**

FILE NAME: **08 DERBY US 5 SB TSS.xls** PLOT DATE: **11/7/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
DERBY SB SHEET 11 SHEET **94** OF **100**