

TOWN TOTAL SIGN SUMMARY SHEET

BARTON-DERBY STPG SIGN (46)

Town Name - Route	County	Town Mileage	NEW SIGNS (SF)		EXISTING SIGNS (EA)				EXIST POST (EA)		SQUARE STEEL (IN)				SQUARE TUBE SIGN POST AND ANCHOR (LF)	TUBULAR STEEL Ø (IN)				
			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE	(LB / FT)			TOTAL POSTS		FOUNDATION	(LB / FT)			
											1.75	2.00	2.50				3.00	3.50	4.00	5.00
						1.88	2.42	3.35					7.60	9.00		10.80	14.60			
Barton US-5 NB	Orleans	10.775	294.60	0.00	55	4	3	70	-	-	0	49	1	50	750	0	0	0	0	0
Barton US-5 SB	Orleans	10.775	282.58	0.00	47	4	3	63	-	-	0	37	1	38	570	0	0	0	0	0
Irasburg US-5 NB	Orleans	4.762	133.10	0.00	19	1	1	32	-	-	0	26	0	26	390	0	0	0	0	0
Irasburg US-5 SB	Orleans	4.762	165.38	0.00	38	1	1	39	-	-	0	23	1	24	360	0	0	0	0	0
Coventry US-5 NB	Orleans	4.892	257.83	0.00	6	2	2	65	-	-	0	27	5	32	480	2	114	0	0	0
Coventry US-5 SB	Orleans	4.892	265.04	0.00	0	1	0	58	-	-	0	25	4	29	435	0	0	0	0	0
Derby US-5 NB	Orleans	5.118	184.25	0.00	104	3	1	53	-	-	0	29	1	30	450	0	0	0	0	0
Derby US-5 SB	Orleans	5.118	261.50	0.00	99	6	5	69	-	-	0	37	1	38	570	0	0	0	0	0

Estimated Mile Markers to be Salvaged and Mounted on new posts = 7 7 9

TOTAL	51.094	1844.29	0.00	368	29	23	458	-	-	0	253	14	267	4005	2	114	0	0	0
-------	--------	---------	------	-----	----	----	-----	---	---	---	-----	----	-----	------	---	-----	---	---	---

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

TYLIN INTERNATIONAL	PROJECT NAME: BARTON-DERBY	PLOT DATE: 11/7/2014
	PROJECT NUMBER: STPG SIGN(46)	DRAWN BY: J. BLANCHARD
	FILE NAME: z12c532TownTotal.dgn	CHECKED BY: K. KERN
	PROJECT LEADER: D. BRYANT	SHEET 100 OF 100
	DESIGNED BY: B. TOOTHAKER	
	TOWN TOTAL SIGN SUMMARY SHEET	