

## SUMMARY OF LONG LINE QUANTITIES BY ROUTE

ROUTE	TOWN	MM	TO	MM	4'' WHITE LINE	MATERIAL	4'' YELLOW LINE	MATERIAL	REMARKS
VT 103	ROCKINGHAM	0.00	-	6.75	70,560	PAINT	0	THERMOPLASTIC	YELLOW THERMO IS STILL GOOD, DO NOT PAINT. *
VT 103	CHESTER	0.00	-	2.57	26,700	PAINT	0	THERMOPLASTIC	YELLOW THERMO IS STILL GOOD, DO NOT PAINT. *
VT 103	CHESTER	4.27	-	9.88	58,840	PAINT	50,060	PAINT	
									*SOME AREAS WERE PAINTED DUE TO FADED LINES.
VT 103	CAVENDISH	0.00	-	3.74	40,050	PAINT	30,955	PAINT	
VT 103	LUDLOW	0.00	-	1.29	13,380	PAINT	12,715	PAINT	
VT 103	LUDLOW	2.86	-	5.78	31,810	PAINT	25,785	PAINT	
VT 103	MT HOLLY	0.00	-	7.86	83,160	PAINT	65,565	PAINT	
VT 103	WALLINGFORD	0.00	-	2.13	22,380	PAINT	21,785	PAINT	
VT 103	SHREWSBURY	0.00	-	4.24	45,170	PAINT	36,425	PAINT	
VT 103	CLARENDON	0.00	-	1.97	20,600	PAINT	14,210	PAINT	
					404,406		275,417		
	TOTAL VT 103				<del>412,650</del>	PAINT	<del>257,500</del>	PAINT	
US 4	RUTLAND TOWN	0.00	-	1.23	16,150	PAINT	12,600	PAINT	
US 4	MENDON	0.00	-	5.93	68,375	PAINT	61,900	PAINT	
US 4	KILLINGTON	0.00	-	8.49	93,390	PAINT	65,811	PAINT	
US 4	BRIDGEWATER	0.00	-	7.50	78,520	PAINT	66,460	PAINT	
US 4	WOODSTOCK	0.00	-	5.65 *	59,219	PAINT	54,704	PAINT	
US 4	WOODSTOCK	7.22	-	9.65	25,300	PAINT	24,940	PAINT	CONTRACTOR APPLIED PAINT MARKINGS TO PAVING PROJECT PERFORMED BY DISTRICT#4 AT WOODSTOCK M.M. 3.369 ON 10/02/12
US 4	HARTLAND	0.00	-	0.77	7,990	PAINT	7,990	PAINT	
US 4	HARTFORD	0.00	-	9.35 *	98,056	PAINT	90,756	PAINT	
					446,078		397,310		
	TOTAL US 4				<del>447,000</del>		<del>385,161</del>		

NOTE: MATERIAL USED FOR PAVEMENT MARKING  
PAINT = WATERBORNE TRAFFIC PAINT

**ROUTE QUANTITIES**  
**SHEET 2**

PROJECT NAME: STATEWIDE  
PROJECT NO.: NHG MARK (206)  
DESIGN FILE NAME: I2b002.dgn  
PROJECT MANAGER: A GAMBLE  
IPARM FILE NAME: I2b002rq2.I

PLOT DATE: 12-MAR-2012  
DRAWN BY: KAS  
SHEET: 4 OF 20