

SUMMARY OF HAND WORK BY ROUTE

ROUTE	TOWN	MM	STENCIL	4" WHITE LINE	8" YELLOW LINE	8" WHITE LINE	STOP BAR	LETTER & SYM.	CROSS WALK	REMOVAL	RR XING	REMARKS
VT 103	CHESTER	1.72	SCHOOL(1)	-	-	-	-	6	-	-	-	
VT 103	CHESTER	1.95	SCHOOL(1)	-	-	-	-	6	-	-	-	
VT 103	CHESTER	7.80	ARROW(5) ONLY(3) YIELD(1)	600 FEET	-	150 FEET	-	22	-	-	-	JCT VT 10
VT 103	CAVENDISH	1.32	LANE REDUCTION ARROWS(3)	-	-	-	-	3	-	-	-	
VT 103	CAVENDISH	2.10		-	-	700 FEET	-	-	-	-	-	
VT 103	CAVENDISH	2.70	RR XING(1)	-	-	-	-	-	-	-	1	
VT 103	CAVENDISH	2.90	RR XING(1)	-	-	-	-	-	-	-	1	
VT 103	LUDLOW	4.05	ARROW(6) ONLY(4)	400 FEET	-	-	-	22	-	-	-	JCT VT 100 NB
VT 103	LUDLOW	5.62	LANE REDUCTION ARROWS(3)	-	-	-	-	3	-	-	-	
VT 103	MT HOLLY	2.40	LANE REDUCTION ARROWS(3)	-	-	-	-	3	-	-	-	
VT 103	SHREWSBURY	2.18	RR XING(1)	-	-	-	-	-	-	-	1	
VT 103	SHREWSBURY	2.45	RR XING(1)	-	-	-	-	-	-	-	1	
VT 103	SHREWSBURY	3.38	LANE REDUCTION ARROWS(3)	-	-	-	-	3	-	-	-	
VT 103	SHREWSBURY	3.79	RR XING(1)	-	-	-	-	-	-	-	1	
VT 103	SHREWSBURY	3.95	RR XING(1)	-	-	-	-	-	-	-	1	
VT 103	CLARENDON	3.95	YIELD MARKINGS(5)	-	150 FEET	250 FEET	15 FEET	5	-	-	-	JCT US 7
				326	215	995	0	52				
	TOTAL VT 103			1,000 FT	150 FT	1,100 FT	15 FT	73			6	
US 2	PLAINFIELD	1.00	CROSSWALK	-	-	-	-	-	22 FEET	-	-	PLAINFIELD HEALTH CENTER
US 2	MARSHFIELD	7.68	LANE REDUCTION ARROWS(3)	-	-	-	-	3	-	-	-	
US 2	MARSHFIELD	7.78	ARROW(2) ONLY(1)	100 FEET	-	-	-	6	-	-	-	JCT VT 232
US 2	CABOT	2.45	LANE REDUCTION ARROWS(3)	-	-	-	-	3	-	-	-	
US 2	CABOT	5.14	LANE REDUCTION ARROWS(3)	-	-	-	-	3	-	-	-	
US 2	DANVILLE	1.73	CROSSWALK	-	-	-	-	-	22 FEET	-	-	WEST DANVILLE STORE
US 2	DANVILLE	2.63	LANE REDUCTION ARROWS(3)	-	-	-	-	3	-	-	-	
US 2	DANVILLE	3.41	LANE REDUCTION ARROWS(3)	-	-	-	-	3	-	-	-	
US 2	DANVILLE	3.46	LANE REDUCTION ARROWS(3)	-	-	-	-	3	-	-	-	
US 2	DANVILLE	5.48	LANE REDUCTION ARROWS(3)	-	-	-	-	3	-	-	-	
US 2	ST JOHNSBURY	1.16	ARROW(3) ONLY(2) STOP(2)	-	-	-	24 FEET	19	-	-	-	JCT TH 7
US 2	ST JOHNSBURY	1.88	STOP(1)	-	-	-	18 FEET	4	-	-	-	IN MEDIAN AT NB OFF RAMP
US 2	ST JOHNSBURY	2.62	STOP(1)	-	-	-	18 FEET	4	-	-	-	IN MEDIAN AT SB OFF RAMP
US 2	ST JOHNSBURY	2.90	ARROW(5) ONLY(4)	-	-	-	-	21	-	-	-	JCT VT 2B
				305			80	74	62			
	TOTAL US 2			100 FT			60 FT	75	44 FT			

NOTE: ALL HAND WORK IS DONE WITH WATERBORNE TRAFFIC PAINT

HAND WORK QUANTITIES SHEET 2

PROJECT NAME: STATEWIDE
PROJECT NO.: NHG MARK (206)

DESIGN FILE NAME: I2b002.dgn
PROJECT MANAGER: A GAMBLE
IPARM FILE NAME: I2b002hw2.I

PLOT DATE: 12-MAR-2012
DRAWN BY: KAS
SHEET: 8 OF 20