SUMMARY OF HAND WORK BY ROUTE

ROUTE	TOWN	MM	STENCIL	4" WHITE LINE	8" YELLOW LINE	8" WHITE LINE	STOP BAR	LETTER & SYM.	CROSS WALK	REMOVAL	RR XING	REMARKS
US 7	SHELBURNE	2.70	STOP BAR + CROSSWALK	-	-	-	50 FEET	-	40 FEET	-	-	JCT WEBSTER RD
US 7	SHELBURNE	3.00	ARROW(5) ONLY(2)	-	-	-	-	13	-	-	-	TURN LANE FOR JUGHANDLE
US 7	SHELBURNE	3.10	ARROW(4) ONLY(3)	-	-	-	80 FEET	16	80 FEET	-	-	JCT LONG MEADOW DR
US 7	SHELBURNE	3.40	ARROW(4) ONLY(2)	-	-	-	-	12	-	-	-	
US 7	SHELBURNE	3.60	ARROW(4) ONLY(2)	-	-	-	-	12	-	-	-	
US 7	SHELBURNE	3.80	ARROW(5) ONLY(4)	-	-	-	80 FEET	21	80 FEET	-	-	JCT EXECUTIVE DR
US 7	SHELBURNE	4.00	ARROW(4) ONLY(2)	-	-	-	-	12	-	-	-	
US 7	SHELBURNE	4.24	ARROW(4) ONLY(3)	-	-	-	80 FEET	16	80 FEET	-	-	JCT HILLCREST RD
US 7	SHELBURNE	4.33	ARROW(4) ONLY(4)	-	-	-	-	20	-	-	-	
US 7	SHELBURNE	4.58	ARROW(4) ONLY(3)	-	-	-	80 FEET	16	80 FEET	-	-	JCT MARTINDALE RD
US 7	SHELBURNE	4.72	ARROW(4) ONLY(3)	-	-	-	80 FEET	16	80 FEET	-	-	JCT LOCUST HILL RD
US 7	SHELBURNE	4.82	ARROW(1) ONLY(1)	-	-	-	-	5	-	-	-	
US 7	SO. BURLINGTON	0.11	ARROW(5) ONLY(5)	-	-	-	80 FEET	25	80 FEET	-	-	JCT ALLEN RD
US 7	SO. BURLINGTON	0.23	ARROW(5) ONLY(5)	-	-	-	80 FEET	25	80 FEET	-	-	JCT HARBOR VIEW RD
US 7	SO. BURLINGTON	0.53	ARROW(6) ONLY(6)	-	-	-	80 FEET	30	80 FEET	-	-	JCT GREEN MTN DR
US 7	SO. BURLINGTON	0.65	ARROW(4) ONLY(4)	-	-	-	-	20	-	-	-	
US 7	SO. BURLINGTON	0.87	ARROW(5) ONLY(5)	-	250 FEET	-	80 FEET	25	80 FEET	-	-	JCT IDX DR
	SHEET TOTALS			-	250 FEET	-	770 FEET	284	760 FEET	-	-	
				8,688	9,804	1,624	1,717	1,211	1,081			
	TOTAL US 7			~~8,300~~ FT	~~6,865~~ FT	~~1,065~~ FT	~~1,730~~ FT	~~1,207~~	~~1,090~~ FT	-	6	

NOTE: ALL HAND WORK IS DONE WITH WATERBORNE TRAFFIC PAINT

HAND WORK

QUANTITIES SHEET 7

PROJECT NAME: **STATEWIDE**
PROJECT NO.: **NHG MARK (206)**
DESIGN FILE NAME: 12b002.dgn
PROJECT MANAGER: A GAMBLE
IPARM FILE NAME: 12b002hw7.i
PLOT DATE: 12-MAR-2012
DRAWN BY: KAS
SHEET: 13 OF 20