

NOTES:

1. ALL MARKINGS SHALL BE PLACED WHERE EXISTING MARKINGS ARE LOCATED EXCEPT WHERE EXISTING MARKINGS OR STENCILS DO NOT CONFORM WITH DETAIL DRAWINGS. MARKINGS THAT DO NOT CONFORM WITH DETAIL DRAWINGS SHALL BE REMOVED AND REPLACED BY NEW MARKINGS.
2. MARKINGS INCLUDE TURN AND CLIMBING LANES, 8 INCH AND 12 INCH WHITE GORE MARKINGS AND 8 INCH YELLOW GORE MARKINGS.
3. EXISTING CENTERLINE MARKINGS LOCATED IN CENTERLINE RUMBLE STRIPS. FOR THE FOLLOWING LOCATIONS THE PAINT APPLICATOR WILL NEED TO BE MODIFIED TO PAINT OVER RUMBLE STRIPS:

US 7 BRANDON MM 5.68 TO LEICESTER MM 1.25
US 7 LEICESTER MM 1.97 TO MIDDLEBURY MM 1.12
US 4 MENDON MM 1.25 TO KILLINGTON MM 2.05
VT 9 MARLBORO MM 0.60 TO BRATTLEBORO MM 1.60
4. ALL MARKINGS DONE ON US 7 IN SHELBURNE AND SO. BURLINGTON SHALL BE DONE AT NIGHT WITH UTO'S. SEE THE SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

**PAVEMENT MARKING
NOTES**

PROJECT NAME: **STATEWIDE**
PROJECT NO.: **NHG MARK (206)**

DESIGN FILE NAME: I2b002.dgn
PROJECT MANAGER: A GAMBLE
IPARM FILE NAME: I2b002pnn.I

PLOT DATE: 12-MAR-2012
DRAWN BY: KAS
SHEET: 15 OF 20