

COMPOSITE QUANTITY SHEET 1

MORRISTOWN BRS 0240(3)S					MORRISTOWN STP HES 030-2(28)				TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	EROSION CONTROL	BRIDGE 1	FULL CE ITEMS	ROADWAY	EROSION CONTROL	CATTLE PASS	FULL CE ITEMS	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
0.50					0.50				1			LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10			
6215					5605				11820			CY	COMMON EXCAVATION	203.15			
180									180			CY	SOLID ROCK EXCAVATION	203.16			
4350									4350			CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27			
75					25				100			CY	EXCAVATION OF SURFACES AND PAVEMENTS	203.28			
2104					526				2630			CY	EARTH BORROW	203.30			
1840					1610				3450			CY	SAND BORROW	203.31			
1130									1130			CY	GRANULAR BORROW	203.32			
240					200				440			CY	TRENCH EXCAVATION OF EARTH	204.20			
					10				10			CY	TRENCH EXCAVATION OF ROCK	204.21			
1					1				2			CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22			
			7				900		907			CY	STRUCTURE EXCAVATION	204.25			
128			545		14		710		1397			CY	GRANULAR BACKFILL FOR STRUCTURES	204.30			
50									50			SY	DRILLING AND BLASTING OF SOLID ROCK SUBGRADE	205.20			
			601						601			CY	COFFERDAM EXCAVATION, EARTH	208.30			
			27						27			CY	COFFERDAM EXCAVATION, ROCK	208.35			
			1						1			LS	COFFERDAM (PIER NO. 1)	208.40			
			1						1			LS	COFFERDAM (PIER NO.2)	208.40			
1270					170				1440			SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10			
3790					3340				7130			CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35			
310					100				410			CY	AGGREGATE SURFACE COURSE	401.10			
22			4		26				52			CWT	EMULSIFIED ASPHALT	404.65			
1					1				2			LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50			
600					1280				1880			TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 70-28)(SBS POLYMER)	490.30			
1					1				2			LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32			
			235						235			CY	CONCRETE, HIGH PERFORMANCE CLASS A (FPQ)	501.33			
			444						444			CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34			
			1						1			LS	FURNISHING EQUIPMENT FOR DRIVING PILING	504.10			
			529						529			LF	STEEL PILING, HP 14 X 117	505.20			
			441000						441000			LB	STRUCTURAL STEEL, CURVED PLATE GIRDER (FPQ)	506.56			
			56295		662				56957			LB	REINFORCING STEEL, LEVEL I	507.11			
			35090						35090			LB	REINFORCING STEEL, LEVEL III	507.13			
			114						114			LF	DRILLING AND GROUTING DOWELS	507.16			
			1						1			LS	SHEAR CONNECTORS (2638 - 7/8" x 7")	508.15			
			30				10		40			GAL	WATER REPELLENT, SILANE	514.10			
			30						30			LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG (FPQ)	516.40			
			743						743			SY	MEMBRANE WATERPROOFING, SPRAY APPLIED	520.10			
			60						60			LF	JOINT SEALER, HOT Poured	524.11			
			454						454			LF	BRIDGE RAILING, GALVANIZED 3 RAIL BOX BEAM (FPQ)	525.335			
			1						1			LS	MAINTENANCE OF STRUCTURES AND APPROACHES	527.10			

PROJECT NAME: MORRISTOWN
 PROJECT NUMBER: BRS 0240(3)S/STP HES 030-2(28)
 FILE NAME: s78f329qty.dgn PLOT DATE: 15-MAY-2017
 PROJECT LEADER: C. CARLSON DRAWN BY: C. BURRALL
 DESIGNED BY: C. BURRALL CHECKED BY: J. LACROIX
 COMPOSITE QUANTITY SHEET 1 SHEET 12 OF 175

REVISION	DATE	BY	DESCRIPTION
△	05/15/2017	VAOT	CHANGED PAY ITEM