

COMPOSITE QUANTITY SHEET 2

MORRISTOWN BRS 0240(3)S					MORRISTOWN STP HES 030-2(28)				TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	EROSION CONTROL	BRIDGE 1	FULL CE ITEMS	ROADWAY	EROSION CONTROL	CATTLE PASS	FULL CE ITEMS	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
			10							10		EACH	BEARING DEVICE ASSEMBLY, HIGH LOAD MULTI-ROTATIONAL	531.15			
							1			1		LS	PRECAST CONCRETE STRUCTURE (8'-0" X 6'-0" X 6'-0" CATTLE PASS)	540.10			
					5					5		CY	CONCRETE, CLASS B	541.25			
			21							21		CY	CONCRETE, CLASS C	541.30			
174										174		LF	18" CPEP(SL)	601.2615			
131										131		LF	24" CPEP(SL)	601.2620			
28					48					76		LF	30" CPEP(SL)	601.2625			
2										2		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18			
1					1					2		EACH	PRECAST REINFORCED CONCRETE MANHOLE WITH CAST IRON COVER	604.21			
					350					350		LF	6 INCH UNDERDRAIN PIPE	605.10			
					100					100		LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20			
					2					2		EACH	UNDERDRAIN FLUSHING BASIN	605.95			
5					25					30		MGAL	DUST CONTROL WITH WATER	609.10			
		140								140		CY	STONE FILL, TYPE I	613.10			
		1030				20				1050		CY	STONE FILL, TYPE II	613.11			
			1350							1350		CY	STONE FILL, TYPE IV	613.13			
			450							450		CY	RIPRAP, HEAVY TYPE	613.15			
					1					1		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10			
20										20		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	618.11			
5										5		TON	BITUMINOUS CONCRETE SIDEWALK	618.15			
96										96		SF	DETECTABLE WARNING SURFACE	618.30			
12					4					16		EACH	YIELDING MARKER POSTS	619.17			
15										15		LF	GATE FOR CHAIN-LINK FENCE, 4 FEET	620.15			
311					541					852		LF	REMOVAL OF EXISTING FENCE	620.55			
163										163		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21			
					322					322		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.215			
					88					88		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	621.217			
1145					245					1390		LF	BOX BEAM GUARDRAIL	621.30			
4					4					8		EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.51			
2										2		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60			
4										4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 3 RAIL BOX BEAM	621.725			
430					370					800		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80			
					44					44		LF	SLEEVES FOR UTILITIES (1 X 12")	625.10			
					52					52		LF	SLEEVES FOR UTILITIES (1 X 18")	625.10			
			1							1		TON	CRUSHED STONE BEDDING	629.54			
					400					400		HR	UNIFORMED TRAFFIC OFFICERS	630.10			
1000					3000					4000		HR	FLAGGERS	630.15			
				0.50				0.50		1		LS	FIELD OFFICE, ENGINEERS	631.10			
				1						1		LS	TESTING EQUIPMENT, CONCRETE	631.16			
				0.50				0.50		1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17			
				2000				2000		4000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26			

PROJECT NAME: MORRISTOWN
PROJECT NUMBER: BRS 0240(3)S/STP HES 030-2(28)
FILE NAME: s78f329qty.dgn PLOT DATE: 12-APR-2017
PROJECT LEADER: C. CARLSON DRAWN BY: C. BURRALL
DESIGNED BY: C. BURRALL CHECKED BY: J. LACROIX
COMPOSITE QUANTITY SHEET 2 SHEET 13 OF 175