

# COMPOSITE QUANTITY SHEET 3

MORRISTOWN BRS 0240(3)S					MORRISTOWN STP HES 030-2(28)				TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	EROSION CONTROL	BRIDGE 1	FULL CE ITEMS	ROADWAY	EROSION CONTROL	CATTLE PASS	FULL CE ITEMS	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
	520									520		HR	EMPLOYEE TRAINEESHIP	634.10			
0.50					0.50					1		LS	MOBILIZATION/DEMOLITION	635.11			
3					3					6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15			
2827					2553					5380		LF	DURABLE 4 INCH WHITE LINE (FPQ)	646.400			
2710					2550					5260		LF	DURABLE 4 INCH YELLOW LINE (FPQ)	646.410			
48										48		LF	DURABLE 12 INCH WHITE LINE (FPQ)	646.460			
					33					33		LF	DURABLE 24 INCH STOP BAR (FPQ)	646.480			
					4					4		EACH	DURABLE LETTER OR SYMBOL (FPQ)	646.490			
		3310				30				3340		SY	GEOTEXTILE UNDER STONE FILL	649.31			
		750				210				960		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515			
		250								250		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61			
		190				80				270		LB	SEED	651.15			
		790				330				1120		LB	FERTILIZER	651.18			
		4				2				6		TON	AGRICULTURAL LIMESTONE	651.20			
		4				2				6		TON	HAY MULCH	651.25			
		830				360				1190		CY	TOPSOIL	651.35			
		990								990		SY	GRUBBING MATERIAL	651.40			
		1								1		LS	EPSC PLAN (BRS 0240(3)S)	652.10			
						1				1		LS	EPSC PLAN (STP HES 030-2(28))	652.10			
		200								200		HR	MONITORING EPSC PLAN (BRS 0240(3)S)	652.20			
						200				200		HR	MONITORING EPSC PLAN (STP HES 030-2(28))	652.20			
		1								1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BRS 0240(3)S)	652.30			
						1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (STP HES 030-2(28))	652.30			
		5660				1790				7450		SY	TEMPORARY EROSION MATTING	653.20			
		80								80		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25			
		60				30				90		CY	VEHICLE TRACKING PAD	653.35			
		2								2		EACH	INLET PROTECTION DEVICE, TYPE I	653.40			
		430								430		LF	BARRIER FENCE	653.50			
		2820				2380				5200		LF	PROJECT DEMARCATION FENCE	653.55			
		70								70		LF	EROSION LOG	653.60			
158					47					205		SF	TRAFFIC SIGNS, TYPE A	675.20			
336					172					508		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341			
37					20					57		EACH	REMOVING SIGNS	675.50			
					11					11		EACH	ERECTING SALVAGED SIGNS	675.60			
13					5					18		EACH	DELINEATOR WITH STEEL POST	676.10			
1					1					2		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50			
20										20		CY	SPECIAL PROVISION (AGGREGATE SURFACE COURSE, TRAIL)	900.608			
			39							39		CY	SPECIAL PROVISION (GEOGRID - COMPRESSIBLE INCLUSION)	900.608			
11										11		CY	SPECIAL PROVISION (RECYCLED ASPHALT SURFACE COURSE)	900.608			
					25000					25000		DL	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(N.A.B.I.)	900.615			

PROJECT NAME: MORRISTOWN  
 PROJECT NUMBER: BRS 0240(3)S/STP HES 030-2(28)  
 FILE NAME: s78f329qty.dgn PLOT DATE: 12-APR-2017  
 PROJECT LEADER: C. CARLSON DRAWN BY: C. BURRALL  
 DESIGNED BY: C. BURRALL CHECKED BY: J. LACROIX  
 COMPOSITE QUANTITY SHEET 3 SHEET 14 OF 175