STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS: EACH	SIGN DIMENSIONS: WIDTH (in)	SIGN DIMENSIONS: HEIGHT (in)	NEW & SALVAGED SIGNS: "A"	NEW & SALVAGED SIGNS: "B"	NEW & SALVAGED SIGNS: SALV SIGN	NEW & SALVAGED SIGNS: SALV TIS	EXIST POST: RETAIN	EXIST POST: SALVAGE	NO. OF POST	FLANGED CHANNEL (LB / FT) 1.12	FLANGED CHANNEL (LB / FT) 2.00	FLANGED CHANNEL (LB / FT) 3.00	SQUARE STEEL (in) 1.75 (LB / FT 1.88)	SQUARE STEEL (in) 2.00 (LB / FT 2.42)	SQUARE STEEL (in) 2.50 (LB / FT 3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) 3.00 (LB / FT 1.30)	TUBULAR ALUMINUM Ø (IN) 4.00 (LB / FT 1.70)	TUBULAR ALUMINUM Ø (IN) 4.0 MOD (LB / FT 1.70)	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT 7.60)	TUBULAR STEEL Ø (IN) 3.50 (LB / FT 9.00)	TUBULAR STEEL Ø (IN) 4.00 (LB / FT 10.80)	TUBULAR STEEL Ø (IN) 5.00 (LB / FT 14.60)	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
OPTION ITEMS																																			
	VT-15																																		
205+27.00 LT	SPEED LIMIT 50	1	24.0	30.0	5.0						1.0					15.0		X															R2-1		SHSM
206+04.00 RT	↑ Wolcott 6	1	72.0	12.0	6.0						2.0						32.0	X															VD1-1A		T-93
	↑ Hardwick 12	1	72.0	12.0	6.0																												VD1-1A		T-93
	Morrisville 2 →	1	72.0	12.0	6.0																												VD1-1A		T-93
207+60.00 LT	↑ Hyde Park 3	1	72.0	12.0	6.0						2.0					36.0		X															VD1-1A		T-93
	↑ Johnson 8	1	72.0	12.0	6.0																												VD1-1A		T-93
	WEST						1.0																										M3-4		SHSM
	VERMONT 15						1.0																												E-136B

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TOTALS	"A"	"B"	SALV SIGN	SALV TIS	RETAIN / SALVAGE / POST	FLANGED CHANNEL 1.12	FLANGED CHANNEL 2.00	FLANGED CHANNEL 3.00	SQUARE STEEL 1.75	SQUARE STEEL 2.00	SQUARE STEEL 2.50	ANCHOR	SLEEVE	TUB. ALUM. 3.00	TUB. ALUM. 4.00	TUB. ALUM. 4.0 MOD	FOUNDATION	TUB. STEEL 3.00	TUB. STEEL 3.50	TUB. STEEL 4.00	TUB. STEEL 5.00	24"	30"	WEIGHT
Units	SF	SF	EA.	SF	XXXXXXXXXXX	FT	FT	FT	FT	FT	FT	XXXXX	EA	LB	LB	LB		LB	LB	LB	LB			
Subtotal						.	.	.	.	51.	32.	XXXXX	.	.	.	.		.	.	.	.			
Total units	SF	SF	EA.	SF	XXXXXXXXXXX	FT			FT					LB			EA.	LB				EA.	EA.	LB
Total	35.	.	2.	.	XXXXXXXXXXX	.			83.					.				.				.	.	.

PROJECT NAME:	MORRISTOWN		
PROJECT NUMBER:	BRS 0240(3)S/STP HES 030-2(28)		
FILE NAME:	s78f329TSS.dgn	PLOT DATE:	12-APR-2017
PROJECT MANAGER:	C. CARLSON	DRAWN BY:	G. ROKES
DESIGNED BY:	C. BURRALL	CHECKED BY:	J. LACROIX
TRAFFIC SIGN SUMMARY SHEET 4		SHEET 71	OF 175