

RECESS Members

- Flexible Material - Easy to install and remove from concrete
- Long-lasting and reusable
- Manufactured from durable urethane



RECESS MEMBER DIMENSIONS

Patterson Recess Member	Anchor Angle	Product Code	WD - Wire Diameter	L - Length	H - Height	W - Width
	90°	TKURM449	.444"	9.00"	3.25"	3"
	90°	TKURM679	.671"	9.00"	3.25"	3"

Note: Urethane can handle temperatures up to 180 degrees. Using a petroleum based form release will drastically shorten the life of a urethane recess member.



UTILITY-LIFT MAGNETIC RECESS MEMBER (1-PIECE)

Our one-piece urethane recess has a magnet embedded in the bottom for easy installation of Utility-Lift Anchors. Available for .444" and .671" anchors.



LIFT PIN MAGNETIC HOLDING PLATE (2-PIECE)

Powerful magnets designed for quick and efficient mounting and holding of recess members to steel forms, to eliminate the need for drilling holes in the form. Recess member and magnet sold separately.

Product Code - TKURIMP679

Vermont Agency of Transportation
RECEIVED
Sheet #1 of 1
 CK'D BY CLB OK'D BY CWC
 February 16, 2018
 RESUBMIT No Approved
 BY C. CARLSON DATE 02/16/18

