DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ALBURGH VT78 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	M4-6	24	12								1																
		F	M1-5	24	24								1																
		F	M2-1	21	15			2.19								1		X							#1	BLACK ON WHITE	X	6	
		F	M1-4	24	24			4.00																			X		
		F	M4-6	24	12			2.00																			GREEN ON WHITE	X		
		F	M1-5	24	24			4.00																					E-136B
WB	0.160	F	VD-062AS	72	16		BUSINESS SIGNS			1				X															
		F	VD-062AS	72	16					1																			
WB	0.140	F	D1-1G	72	10		DESTINATION SIGNS						1		X														
		F	D1-1A	72	10								1																
		F	D1-1A	72	10								1																
		F	D1-1M	72	10								1																
		F	D1-1M	72	10								1																
		F	VD1-1A	72	12			6.00								2		X										4	
		F	VD1-1A	72	12			6.00																				4	
							SHEET TOTALS	24.19	0.00	2	0	0	7	0	0	3	45.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	153.8	0.0	19	0	0	31	0	0	17	255.0			0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Statewide-NW Region
PROJECT NUMBER: STPG SIGN(42)
FILE NAME: Alburgh VT78WB.xls
PROJECT MANAGER: A. Gamble
DESIGNED BY: T. Guazzoni
ALBURGH VT78 WB SHEET 4
PLOT DATE: 8/30/2012
DRAWN BY: T. Guazzoni
CHECKED A. Gamble
SHEET 16 OF 69