DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SWANTON VT78 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X								GREENWICH ST (TH-119)		7	
EB	6.984	D	R1-1	30	30		STOP						1		X														
		D	R1-1	30	30			6.25								1		X								GREENWICH ST (TH-119)	X		
EB	7.057	C	VR-017	24	30								~~1~~		~~X~~														
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X								NEW ST (TH-129)		7	
EB	7.060	D	R1-1	30	30		STOP						1		X														
		D	R1-1	30	30			6.25								1		X								NEW ST (TH-129)	X		
EB	7.152	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X								LIBERTY ST (TH-126) INSTALL SIGN AT START OF WHITE PICKET FENCE		7	
EB	7.155	D	R1-1	30	30		STOP						1		X														
		D	R1-1	30	30			6.25								1		X								LIBERTY ST (TH-126)	X		
EB	7.195	A	R8-3A	8	8								1		X														
		A	R8-3A	24	24			4.00								1		X									X		
EB	7.220	A	W11-8	30	30								1	X															
		A	W11-8	30	30			6.25																			X		
EB	7.223	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X								PINE ST (TH-130)		7	
							SHEET TOTALS	49.00	0.00	0	0	~~0~~	6	0	0	8		120.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	445.7	0.0	97	4	4	104	0	0	57		855.0		0		0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Statewide-NW Region**
PROJECT NUMBER: **STPG SIGN(42)**

FILE NAME: **Swanton VT78EB.xls**
PROJECT MANAGER: **A. Gamble**
DESIGNED BY: **T. Guazzoni**
SWANTON VT78 EB SHEET 16

PLOT DATE: **8/30/2012**
DRAWN BY: **T. Guazzoni**
CHECKED **A. Gamble**
SHEET **34** OF **69**