| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION SHSM | SIGN DETAIL LOCATION PROJECT SHEET # | SIGN DETAIL LOCATION STANDARD SHEET # |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **SWANTON VT78 WB** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| | | H | R1-1 | 30 | 30 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | H | R1-1 | 30 | 30 | | | 6.25 | | | | | | | | | | | | | | | | | | PINE ST (TH-130) | X | | |
| WB | 7.185 | F | R8-3A | 8 | 8 | | | | | | | | 1 | X | | | | | | | | | | | | | | | |
| | | F | R8-3 | 24 | 24 | | | 4.00 | | | | | | | | | | | | | | | | | | | X | | |
| WB | 7.152 | F | D3-1 | UNK | UNK | | LIBERTY ST STREET NAME SIGN | | | | 1 | 1 | 1 | | X | 1 | | X | | | | | | | | | | | |
| | | G | D3-1 | UNK | UNK | | FIRST ST STREET NAME SIGN | | | | 1 | 1 | 1 | | | | | | | | | | | | | | | | |
| | | H | R1-1 | 30 | 30 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | H | R1-1 | 30 | 30 | | | 6.25 | | | | | | | | | | | | | | | | | | LIBERTY ST (TH-126) | X | | |
| WB | 7.085 | F | R8-3A | 8 | 8 | | | | | | | | 1 | | X | | | | | | | | | | | | | | |
| | | F | R8-3 | 24 | 24 | | | 4.00 | | | | | | | | 1 | | X | | | | | | | | | X | | |
| WB | 7.057 | F | D3-1 | UNK | UNK | | NEW ST STREET NAME SIGN | | | | 1 | 1 | 1 | | X | 1 | | X | | | | | | | | | | | |
| | | G | D3-1 | UNK | UNK | | FIRST ST STREET NAME SIGN | | | | 1 | 1 | 1 | | | | | | | | | | | | | | | | |
| | | H | R1-1 | 30 | 30 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | H | R1-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | | | | | | | | | NEW ST (TH-129) | X | | |
| WB | 7.04 | F | VD-062AS | 72 | 16 | | BUSINESS SIGN | | | 1 | | | | X | | | | | | | | | | | | | | | |
| **SIGN SUMMARY SHEET** | | | | | | | SHEET TOTALS | 26.75 | 0.00 | 1 | 4 | 4 | 9 | 0 | 0 | 4 | | 60.0 | | 0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | FT | | EA | LB | LB | LB | LB | | | | | |
| VERMONT AGENCY OF TRANSPORTATION | | | | | | | TOWN DIRECTIONAL TOTALS | 334.3 | 0.0 | 73 | 19 | 19 | 89 | 0 | 0 | 45 | | 675.0 | | 0 | | 0.0 | | | | | | | |

PROJECT NAME: **Statewide-NW Region**
PROJECT NUMBER: **STPG SIGN(42)**

FILE NAME: **Swanton VT78WB.xls**
PROJECT MANAGER: **A. Gamble**
DESIGNED BY: **T. Guazzoni**
SWANTON VT78 WB SHEET 5

PLOT DATE: **8/30/2012**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **A. Gamble**
SHEET **44** OF **69**