DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SWANTON VT78 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	VW-054L	30	30			6.25																				7	
WB	5.830	F	R2-1	24	30								1		X													
		F	R2-1	24	30			5.00								1		X								X		
WB	5.630	F	R2-1	24	30								1		X													
		F	R2-1	24	30			5.00								1		X								X		
WB	5.295	F	R2-1	24	30		SPEED LIMIT 50			1				X														
WB	4.371	F	VW-512	30	30		WILDLIFE AREA			1		I		X														
		F	W7-3A	24	18		NEXT 3 MILES			1																		
WB	4.205	G	VR-023B	24	30								~~1~~ 2		X													
		G	VR-023B	24	30			5.00								1		X									6	
WB	4.100	F	W1-2R	30	30		RIGHT CURVE				1		1		X											RELOCATE SIGN TO MP 4.05+/-		
WB	4.05	F	W1-2R	30	30		RIGHT CURVE					1				1		X								INSTALL RELOCATED SIGN FROM MP 4.10+/-		
WB	3.875	F	R2-1	24	30		SPEED LIMIT 50			1		I		X														
WB	3.271	F	W1-2L	30	30		LEFT CURVE					I	1		X													
WB	3.151	F	W1-2L	30	30			6.25								1		X								INSTALL 630'+/- WEST OF EXISTING SIGN	X		
							SHEET TOTALS	27.50	0.00	4	1	~~1~~ 4	~~5~~ 6	0	0	5		75.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	334.3	0.0	73	19	19	89	0	0	45		675.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Statewide-NW Region**
PROJECT NUMBER: **STPG SIGN(42)**

FILE NAME: **Swanton VT78WB.xls**
PROJECT MANAGER: **A. Gamble**
DESIGNED BY: **T. Guazzoni**
SWANTON VT78 WB SHEET 14

PLOT DATE: **8/30/2012**
DRAWN BY: **T. Guazzoni**
CHECKED **A. Gamble**