DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
HIGHGATE US7 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	6.140	A	W1-8	18	24		CHEVRON			1				X															
NB	6.150	A	W1-8	18	24		CHEVRON			1				X															
NB	6.170	A	W1-8	18	24		CHEVRON			1				X															
NB	6.180	A	D1-1A	72	12		DESTINATION SIGNS			1				X															
		A	D1-1A	72	12					1																			
NB	6.180	A	M3-3	24	12		SOUTH				1	1	1	X		1		X							#2			6	
		A	M1-1	24	24		INTERSTATE 89				1	1	1																
		A	M6-1	21	15		LEFT ARROW				1	1	1																
		A	M4-6	24	12		END					1														INSTALL RELOCATED SIGNS ON RIGHT SIDE OF EXISTING ROUTE MARKER ASSEMBLY			
		A	M1-4	24	24		US7					1																	
							SHEET TOTALS	0.00	0.00	5	3	5	3	0	0	1		15.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	108.3	0.0	57	5	5	19	0	0	24		360.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Statewide-NW Region**
PROJECT NUMBER: **STPG SIGN(42)**

FILE NAME: **Highgate us7NB.xls**
PROJECT MANAGER: **A. Gamble**
DESIGNED BY: **T. Guazzoni**
HIGHGATE US7 NB SHEET 7

PLOT DATE: **8/30/2012**
DRAWN BY: **T. Guazzoni**
CHECKED **A. Gamble**