TOWN TOTAL SIGN SUMMARY SHEET

STATEWIDE-NW REGION STPG SIGN (42)

TOWN NAME		TOWN MILEAGE	NEW SIGNS (SF) TYPE A	NEW SIGNS (SF) TYPE B	EXISTING SIGNS (EA) RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE			NUMBER OF NEW POSTS (EA) 1.75" (LB / FT) 1.88	2" (LB / FT) 2.42	2.5" (LB / FT) 3.35	TOTAL POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60
ALBURGH VT78 EB	GRAND ISLE	124.75	~~132.8~~	0	18	0	1 ~~0~~	~~18~~	24		0	24	0	24	0	~~360~~	354 0	0				
ALBURGH VT78 WB	GRAND ISLE	3.329	153.8	0	19	0	1 ~~0~~	~~31~~	32		0	15	2	17	0	~~225~~	253 30	0				
SWANTON VT78 EB	FRANKLIN	440.24	~~445.7~~	0	97	4	10 ~~4~~	~~104~~	101		0	57	2	59	0	~~855~~	893 30	0				
SWANTON VT78 WB	FRANKLIN	7.807 334.33	~~334.3~~	0	73	19	24 ~~19~~	~~89~~	94		0	45	0	45	0	~~675~~	653 0	0				
HIGHGATE US7 NB	FRANKLIN	108.34	~~108.3~~	0	57	5	5	~~19~~	16		0	24	0	24	0	~~360~~	310 0	0				
HIGHGATE US7 SB	FRANKLIN	6.208 60.94	~~60.9~~	0	37	3	4 ~~3~~	~~14~~	8		0	9	0	9	0	~~135~~	147 0	0				
				Sub-Total		31	~~31~~ 45	275				**SUB TOTALS**			0	~~2610~~ 2618	60					
TOTAL ESTIMATED SALVAGED MILEMARKER PLAQUES						15	~~15~~	~~15~~														
		TOTAL =	~~1235.8~~ 1222.4	0	301	46	~~46~~ 45	~~290~~ 275			0	~~174~~	4	~~178~~	~~2670~~ 2618			0	0.0	0.0	0.0	0.0

PROJECT NAME: STATEWIDE - NORTHWEST REGION

PROJECT NUMBER: STPG SIGN (42)

FILE NAME: 12B120.DGN
PROJECT LEADER: A. GAMBLE
DESIGNED BY: T. GUAZZONI
TOWN TOTAL SIGN SUMMARY SHEET

PLOT DATE: 17-AUG-2012
DRAWN BY: T. GUAZZONI
CHECKED BY: A. GAMBLE
SHEET 69 OF 69