

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	BRIDGE	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							250				250		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
							4				4		EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.51				
							4				4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 2 RAIL BOX BEAM	621.72				
							570				570		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
							250				250		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
							168				168		HR	FLAGGERS	630.15				
									1		1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1		1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1		1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									3000		3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
									520		520		HR	EMPLOYEE TRAINEESHIP	634.10				
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
							4				4		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
							1425				1425		LF	4 INCH WHITE LINE	646.20				
							1500				1500		LF	4 INCH YELLOW LINE	646.21				
							575				575		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								375			375		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								140			140		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								20			20		LB	SEED	651.15				
								130			130		LB	FERTILIZER	651.18				
								0.5			0.5		TON	AGRICULTURAL LIMESTONE	651.20				
								0.5			0.5		TON	HAY MULCH	651.25				
								70			70		CY	TOPSOIL	651.35				
							450				450		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								50			50		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								1275			1275		SY	TEMPORARY EROSION MATTING	653.20				
								12			12		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
								30			30		CY	VEHICLE TRACKING PAD	653.35				
								1025			1025		LF	PROJECT DEMARCATION FENCE	653.55				
							1				1		SF	TRAFFIC SIGNS, TYPE A	675.20				
							16				16		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
							4				4		EACH	REMOVING SIGNS	675.50				
							1				1		EACH	ERECTING SALVAGED SIGNS	675.60				
							1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
										25	25		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET) (FPQ)	900.608				
										425	425		CY	SPECIAL PROVISION (MECHANICALLY STABILIZED EARTH ABUTMENT BACKFILL SYSTEM) (FPQ)	900.608				
										35	35		CY	SPECIAL PROVISION (ULTRA HIGH PERFORMANCE CONCRETE) (FPQ)	900.608				
							4				4		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620				

REV	DATE	DESCRIPTION
△	10/13/2015	QUANTITY REVISION



PROJECT NAME: WAITSFIELD
PROJECT NUMBER: BRF 013-4(39)
FILE NAME: z12b136frm.dgn
PROJECT LEADER: R.YOUNG
DESIGNED BY: D.KULL
QUANTITY SHEET #2

PLOT DATE: 10/13/2015
DRAWN BY: S.MERKWAN
CHECKED BY: T.KENDRICK
SHEET 6 OF 69