



LAYOUT
 30 0 30
 SCALE: 1" = 30'-0"

MARK	STATION	OFFSET	PHASING	NORTHING	EASTING	REMARKS	POLE NUMBER
UP#1	12+23	26' LT	PRE-CONSTRUCTION	1553141.47	609759.27	REMOVE EXISTING GUYS. ADD SPAN GUY AND DEAD END GUY.	123142/230/52
UP#2	13+28	21' LT	PRE-CONSTRUCTION	1553124.05	609863.93	REMOVE EXISTING UTILITY POLE AND LINES.	1311/229/51
UP#3	13+14	33' LT	PRE-CONSTRUCTION	1553114.43	609847.37	INSTALL NEW UTILITY POLE. ADD NEW GUY. RELOCATE ALL LINES FROM UP#2 TO UP#3.	NEW POLE
UP#4	15+37	22' LT	PRE-CONSTRUCTION	1553076.96	610067.21	REMOVE EXISTING UTILITY POLE AND LINES.	1310/228/3/50
UP#5	15+37	40' LT	PRE-CONSTRUCTION	1553059.87	610063.37	INSTALL NEW UTILITY POLE WITH NEW 18' GUY WIRE. RELOCATE ALL LINES FROM UP#4 TO UP#5.	NEW POLE
GP#1	13+04	25' RT	PRE-CONSTRUCTION	1553174.52	609850.64	REMOVE EXISTING GUY POLE AND GUYS.	1313/229/30/51S
GP#2	12+16	22' RT	PRE-CONSTRUCTION	1553188.27	609773.09	INSTALL NEW GUY POLE WITH NEW GUY WIRE TO UP#1, AND NEW 18' SLOPE GUY.	NEW POLE

RIGHT OF WAY NEEDS

1. PERMANENT 12.5' AERIAL TRIM RIGHTS FOR RELOCATED ELECTRICAL LINES.
2. PERMANENT EASEMENT FOR GUY WIRE ATTACHED TO UP#5.
3. PERMANENT ACCESS EASEMENT TO UP#5.
4. PERMANENT AERIAL TRIM RIGHTS FOR RELOCATED ELECTRICAL ACROSS MAD RIVER

PROJECT NAME: WAITSFIELD	PLOT DATE: 8/24/2015
PROJECT NUMBER: BRF 013-4(39)	DRAWN BY: S. MERKWAN
FILE NAME: z12b136u1.dgn	DESIGNED BY: D. KULL
UTILITY RELOCATION PLAN	CHECKED BY: T. KENDRICK
	SHEET 69 OF 69

