

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES						TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
	ROADWAY	EROSION CONTROL	RAILROAD	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
				1		1		LS	BEGIN OPTION DD					
				1		1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB NO. 2)	540.10				
				1		1		LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE)(APPROACH SLAB NO. 2)	900.645				
									END OPTION DD					
	1					1		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42				
	1					1		MGAL	DUST CONTROL WITH WATER	609.10				
		465	400			865		CY	STONE FILL, TYPE I	613.10				
	155					155		LF	PRECAST REINFORCED CONCRETE CURB, TYPE B	616.26				
				104		104		LF	SNOW BARRIER	620.75				
	330					330		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
	175					175		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205				
	4					4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
	4					4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 2 RAIL BOX BEAM	621.72				
	57					57		LF	REMOVE AND RESET GUARDRAIL	621.75				
	480					480		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
			2			2		MFBM	INSULATION BOARD	622.10				
	480					480		HR	FLAGGERS	630.15				
					1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
					1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
					1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
					3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
	1					1		LS	MOBILIZATION/DEMobilIZATION	635.11				
	1					1		LS	TRAFFIC CONTROL	641.10				
	2					2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
	1090					1090		LF	4 INCH WHITE LINE	646.20				
	1090					1090		LF	4 INCH YELLOW LINE	646.21				
		1025	1150			2175		SY	GEOTEXTILE UNDER STONE FILL	649.31				
		1390				1390		SY	GEOTEXTILE FOR SILT FENCE	649.51				
		6.75				6.75		LB	SEED	651.15				
		50				50		LB	FERTILIZER	651.18				
		0.25				0.25		TON	AGRICULTURAL LIMESTONE	651.20				
		0.25				0.25		TON	HAY MULCH	651.25				
		70				70		CY	TOPSOIL	651.35				
		1075				1075		SY	GRUBBING MATERIAL	651.40				
		1				1		LS	EPSC PLAN	652.10				
		160				160		HR	MONITORING EPSC PLAN	652.20				
		1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
		515				515		SY	TEMPORARY EROSION MATTING	653.20				
		30				30		CY	VEHICLE TRACKING PAD	653.35				
		2900				2900		LF	PROJECT DEMARCATION FENCE	653.55				

REV.	DESCRIPTION	DATE
△	CONTRACTOR-FABRICATED PRECAST	12/01/2014



PROJECT NAME:	CASTLETON
PROJECT NUMBER:	BRF 015-2(10)
FILE NAME: z12b138qs.dgn	PLOT DATE: 11/17/2014
PROJECT LEADER: S.E. BURBANK	DRAWN BY: M.C. SCOTT
DESIGNED BY: E.A. FIALA	CHECKED BY: E.A. FIALA
QUANTITY SHEET #2	SHEET 10 OF 82