



MESSAGES FOR PORTABLE CHANGEABLE MESSAGE SIGNS (PCMS)

MESSAGE 1	MESSAGE 2	
<b>VT 11</b>	<b>MM DD</b>	(DATE) *
<b>BRIDGE</b>	<b>THRU</b>	
<b>CLOSED</b>	<b>MM DD</b>	(DATE) *

\* - MONTH SHALL BE SPELLED OUT - JUNE 10, NOT 6/10

LEGEND

- - TYPE III BARRICADE
- ▣ - TYPE III BARRICADE (MOD.)
- ▬ - TEMPORARY TRAFFIC BARRIER
- PCMS - PORTABLE CHANGEABLE MESSAGE SIGN

NOTES:

1. THE NUMBER OF TYPE III BARRICADES AND OTHER TRAFFIC CONTROL DEVICES SHOWN ARE FOR ILLUSTRATIVE PURPOSES ONLY. THE ACTUAL NUMBER REQUIRED ARE TO BE DETERMINED BASED ON INDIVIDUAL ROADWAY CLOSURE REQUIREMENTS.
2. PORTABLE CHANGEABLE MESSAGE SIGNS (PCMS) SHALL BE PLACED OFF THE EDGE OF THE ROADWAY, OUTSIDE THE CLEAR ZONE, BUT SHALL BE VISIBLE FROM THE ROADWAY. ANY VEGETATION THAT INTERFERES WITH VISIBILITY OF THE PCMS SHALL BE REMOVED. REMOVAL OF THE VEGETATION SHALL BE INCIDENTAL TO ITEM 641.17, "PORTABLE CHANGEABLE MESSAGE SIGN RENTAL".
3. THE PORTABLE CHANGEABLE MESSAGE SIGNS (PCMS) SHALL DISPLAY THE MESSAGE SHOWN TWO WEEKS (14 DAYS) PRIOR TO THE CLOSURE OF THE BRIDGE. THE PCMS SHALL NOT BE A PART OF THE DETOUR AND SHALL BE REMOVED ONCE THE DETOUR IS IMPLEMENTED AND THE BRIDGE IS CLOSED.
4. TEMPORARY TRAFFIC BARRIER SHALL MEET THE REQUIREMENTS OF SECTION 621 AND WILL BE INCLUDED FOR PAYMENT UNDER CONTRACT ITEM 900.645 SPECIAL PROVISION (TRAFFIC CONTROL, ALL - INCLUSIVE)

PROJECT NAME:	ANDOVER
PROJECT NUMBER:	BHF 016-1(29)
FILE NAME:	I2bi40/STR/I2bi40derour.dgn
PROJECT LEADER:	C. CARLSON
DESIGNED BY:	D. PETERSON
PROJECT SITE TRAFFIC CONTROL	
PLOT DATE:	06-JAN-2015
DRAWN BY:	G. ROKES
CHECKED BY:	D. PETERSON
SHEET	16 OF 48