

COMPOSITE QUANTITY SHEET 3

WARDSBORO-JAMAICA ER STP 013-1(17)				WARDSBORO BF 013-1(21)			WARDSBORO BF 013-1(22)			TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	FULL C.E. ITEMS		ROADWAY	EROSION CONTROL	BRIDGE	ROADWAY	EROSION CONTROL	BRIDGE	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
													BEGIN OPTION EE					
60										60		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492				
60										60		EACH	DURABLE LETTER OR SYMBOL, EPOXY PAINT	646.493				
60										60		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494				
													END OPTION EE					
115400										115400		LF	TEMPORARY 4 INCH WHITE LINE	646.600				
113700										113700		LF	TEMPORARY 4 INCH YELLOWLINE	646.610				
300										300		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682				
60										60		EACH	TEMPORARY LETTER OR SYMBOL	646.690				
5750										5750		EACH	LINE STRIPING TARGETS	646.76				
28550										28550		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
14500						125				14700		SY	GEOTEXTILE UNDER STONE FILL	649.31				
3100					120			130		3350		SY	GEOTEXTILE FOR SILT FENCE	649.51				
					40			45		85		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
550					5			7		562		LB	SEED	651.15				
					5			7		12		LB	SEED, WINTER RYE	651.17				
3375					40			50		3485		LB	FERTILIZER	651.18				
14					1			1		16		TON	AGRICULTURAL LIMESTONE	651.20				
14					1			1		16		TON	HAY MULCH	651.25				
710					40			65		815		CY	TOPSOIL	651.35				
5900						125			40	6065		SY	GRUBBING MATERIAL	651.40				
					1					1		LS	EPSC PLAN (BF 013-1(21))	652.10				
								1		1		LS	EPSC PLAN (BF 013-1(22))	652.10				
					40			40		80		HR	MONITORING EPSC PLAN	652.20				
					1					1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BF 013-1(21))	652.30				
								1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BF 013-1(22))	652.30				
35400					350			570		36320		SY	TEMPORARY EROSION MATTING	653.20				
					60			60		120		CY	VEHICLE TRACKING PAD	653.35				
					1			1		2		EACH	FILTER BAG	653.45				
5100					230					5330		LF	BARRIER FENCE	653.50				
					80			300		380		LF	PROJECT DEMARCATION FENCE	653.55				
5100										5100		LF	EROSION LOG	653.60				
258										258		SF	TRAFFIC SIGNS, TYPE A	675.20				
2730										2730		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
174										174		EACH	REMOVING SIGNS	675.50				
87										87		EACH	ERECTING SALVAGED SIGNS	675.60				
98										98		EACH	DELINEATOR WITH STEEL POST	676.10				
77										77		EACH	REMOVAL OF EXISTING DELINEATOR	676.12				
1										1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
						105			90	195		CY	SPECIAL PROVISION (STONE FILL, STREAM BED MATERIAL)	900.608				

PROJECT NAME: WARDSBORO-JAMAICA	
PROJECT NUMBER: ER STP 013-1(17) / BF 013-1(21) / BF 013-1(22)	
FILE NAME: dl2b236_frm.dgn	PLOT DATE: 3/31/2014
PROJECT LEADER:	DRAWN BY: B. KIPP
DESIGNED BY: B. KIPP / J. SALVATORI	CHECKED BY: A. KEMPTON
COMPOSITE QUANTITY SHEET 3	SHEET 6 OF 444